

EASTON RACQUET CLUB EXPANSION

36 WIMBLEDON LANE
EASTON, CONNECTICUT

DRAWING PACKAGE:

SURVEY DRAWINGS

MAP OF PROPERTY (BOUNDARY, TOPOGRAPHIC & WETLANDS)


CIVIL ENGINEERING DRAWINGS

- C-1 GENERAL LEGEND, ABBREVIATIONS & NOTES
- C-2 SITE DEVELOPMENT & GRADING PLAN
- C-3 WETLANDS IMPACT PLAN
- C-4 CONSTRUCTION SPECIFICATIONS & STANDARDS AND TEST HOLE DATA AND SEPTIC DETAILS
- C-5 (A&B) SEDIMENT & EROSION CONTROL PLAN
- C-5C SEDIMENT & EROSION CONTROL NARRATIVE
- C-5D SEDIMENT & EROSION CONTROL CONSTRUCTION STANDARDS
- C-5E SEDIMENT & EROSION CONTROL DETAILS, & MISC. SITE DETAILS
- C-6A PICKLEBALL COURT DETAILS
- C-6B PADDLE BALL COURT DETAILS
- C-7A TENNIS COURTS & PICKLE BALL COURTS PHOTOMETRIC AND LIGHTING DETAILS
- C-7B TENNIS COURTS & PICKLE BALL COURTS SITE LIGHTING CUT SHEETS
- C-7C PADDLE BOARD COURTS PHOTOMETRIC AND LIGHTING DETAILS
- C-7D PADDLE BOARD COURTS SITE LIGHTING CUT SHEETS


OWNED AND DEVELOPED BY:

Easton Racquet Club, Inc.
36 Wimbledon Lane
P.O. Box 152
Easton, CT 06612

CIVIL ENGINEERS & LAND SURVEYORS:




800 Main Street South · Southbury, Ct. 06488 · (203) 267-1046 · Fax (203) 267-1547
ENGINEERING · PLANNING · SURVEYING · DEVELOPMENT SERVICES



MARK E. LANCOR, P.E. #12369

Issued to	Date	Approved
Inland Wetlands	2/15/21	3/23/21
Planning	4/2/21	-
Last Revised	3/26/21	-




LOCATION MAP

SCALE: 1" = 1000'

NOTES:

- This map has been prepared pursuant to the Regulations of Connecticut State Agencies Sections 20-300b-1 through 20-300b-20 and the "Standards for Surveys and Maps in the State of Connecticut" as adopted by the Connecticut Association of Land Surveyors, Inc. on September 26, 1996.
 - Type of Survey: **Property**
 - Boundary Determination Category: **Dependent Resurvey**
 - Class of Accuracy: **A-2**
- Zone: (District B).
- Area of Parcel = 437,865 square feet or 10.052 acres.
- Owner: Easton Racquet Club, Inc.
- Topography was obtained in the field by DYMAR on October 30, 2001.
- Vertical elevations are based on an assumed datum.
- Contour interval is two (2) feet.
- All monumentation found or set is depicted or noted hereon.
- The inland wetlands shown have been flagged in the field by Environmental Planning Associates and located by accurate survey.
- Parcel is located in Zones A&C, as shown on the Flood Insurance Rate Map, Community Panel Number 090006 0005 B, Effective Date September 30, 1983, for the Town of Easton, Fairfield County, CT.
- This survey does not include the location of any underground improvements or encroachments, subsurface utility lines or buried debris. Nor does it necessarily reflect the existence of any waste dumps or hazardous materials. The underground items depicted or noted are approximate and not guaranteed. Notify "CALL BEFORE YOU DIG" 1-800-922-4455 prior to any excavation operations.
- Rights to occupancy or possession by any indian nation or tribe of indians or the claim of any governmental body have not been investigated by this office.
- This property is subject to any and all local, state and federal ordinances, statutes, rules and/or regulations, restrictions, public or private law or easement(s); or claims of adverse possession which may affect the premises.
- Map References:
 - "Subdivision For The Easton Racquet Club, Easton, Conn., Scale 1"=100", Dated Sept. 19, 1972, by The Huntington Company, Engineers & Surveyors, Fairfield, Conn."
- All bearings reference the map entitled "Easton Racquet Club, Inc. Wimbledon Lane, Easton, Conn., Site Plan, Scale 1"=50", Dated Feb. 28, 1973, Revised to May 23, 1986, Drawing Number 1, by Robert W. Graf, Consulting Engineer, Staples Rd., Easton, Conn."

N/F
BRIDGEPORT
HYDRAULIC
COMPANY




N/F
RICHARD P. & MARY E. SABATINI

WIMBLEDON LANE

MAP OF PROPERTY
PREPARED FOR
EASTON RACQUET CLUB, INC.
36 WIMBLEDON LANE EASTON, CT
OCTOBER 30, 2001 SCALE: 1"=40'
SHEET 1 OF 1

DATE	REVISION
11/04/20	UPDATED TOPOGRAPHY
10/25/10	ADDITIONAL LOCATIONS
01/13/09	ADDITIONAL LOCATIONS
10/07/08	ADDITIONAL LOCATIONS
9/21/05	ADDED EASEMENT TO TOWN & REF.
11/01/04	UPDATE-CHECK BOUNDARY



800 Main Street South - Southbury, Ct. 06488-2210 • (203) 267-1046 • Fax (203) 267-1547
ENGINEERING • PLANNING • SURVEYING • DEVELOPMENT SERVICES

FIELD BOOK NO.	003	PROJECT NO.	00335
----------------	-----	-------------	-------

To the best of my knowledge and belief, this map is substantially correct as noted hereon.

#12326
STEVEN M. GABRIELE, L.S. REG. NO.
NOT VALID UNLESS EMBOSSED SEAL IS AFFIXED HERETO

DESIGN DATA - CLUB HOUSE B100a

1. SYSTEM IS DESIGNED FOR A 7 TENNIS COURTS @ 150 GPD/COURT FOR TOTAL 1,050 GPD.
2. MINIMUM SIZE SEPTIC TANK REQUIRED BY THE T.A.H.D. IS 1,250 GALLON.
3. SIZE OF EXISTING SEPTIC TANK IS 1,250 GALLONS.
4. SYSTEM IS DESIGNED BASED ON A PERCOLATION RATE OF 1" IN 20.1 TO 30 MINUTES.
5. MINIMUM SIZE OF LEACHING SYSTEM REQUIRED BY THE STATE HEALTH CODE IS 1,050 GPD /0.9 GPD/SFT = 1,167 SQUARE FEET OF EFFECTIVE AREA.
6. SIZE OF SYSTEM PROVIDED IS 84 LINEAR FEET OF 24" HIGH GREENLEACH FILTER GLF 24.62 WITH AN APPLICATION RATE OF 14 SFT/LF, SFT PROVIDED = (84 LF) x (14 SFT/LF) = 1,176 SFT.
7. MINIMUM LEACHING SPREAD NOT REQUIRED, NO RESTRICTIVE LAYERS.
8. MINIMUM LEACHING SPREAD PROVIDED IS: 84 L.F.
9. SYSTEM "WAS NOT" DESIGNED FOR GARBAGE GRINDER USE.
10. SYSTEM "WAS NOT" DESIGNED FOR A BATH TUB WITH A CAPACITY GREATER THAN 100 GALLONS. IF ANYMORE ARE TO BE INSTALLED CONTACT THE DESIGN ENGINEER FOR REQUIRED INCREASE TO THE SEPTIC TANK AND/OR LEACHING AREAS. ALL CHANGES MUST BE APPROVED BY THE DESIGN ENGINEER AND LOCAL HEALTH DEPARTMENT OFFICIALS.
11. LOT IS SERVED BY PRIVATE WELL.

DESIGN DATA - POOL HOUSE B100a

1. SYSTEM IS DESIGNED FOR 36 BATHERS @ 10GPD/BATHER = 360 GPD.
2. MINIMUM SIZE SEPTIC TANK REQUIRED BY THE T.A.H.D. HEALTH DEPARTMENT IS 1,000 GALLON.
3. SIZE OF EXISTING SEPTIC TANK IS 1,000 GALLONS.
4. SYSTEM IS DESIGNED BASED ON A PERCOLATION RATE OF 1" IN 30.1 TO 45 MINUTES.
5. MINIMUM SIZE OF LEACHING SYSTEM REQUIRED BY THE STATE HEALTH CODE IS 360 GPD/0.7 GPD/SFT = 515 SQUARE FEET OF EFFECTIVE AREA.
6. SIZE OF SYSTEM PROVIDED IS 96 LINEAR FEET OF 12" HIGH INFILTRATOR QUICK4 STANDARD (SIDE-BY-SIDE GALLERY CONFIGURATION) WITH AN APPLICATION RATE OF 5.9 SFT/LF, ELA PROVIDED = (96 LF) x (5.9 SFT/LF) = 566 SFT.
7. MINIMUM LEACHING SPREAD REQUIRED BY STATE HEALTH CODE IS: (FLOW: 360 GPD, PERC: 1"/40 MIN., SLOPE 11% R.L. 26"); (HF) X (FF) X (PF) = (26) X (1.2) X (3) = 93.6 L.F.
8. MINIMUM LEACHING SPREAD PROVIDED IS: 96 L.F.
9. SYSTEM "WAS NOT" DESIGNED FOR GARBAGE GRINDER USE.
10. SYSTEM "WAS NOT" DESIGNED FOR A BATH TUB WITH A CAPACITY GREATER THAN 100 GALLONS. IF ANYMORE ARE TO BE INSTALLED CONTACT THE DESIGN ENGINEER FOR REQUIRED INCREASE TO THE SEPTIC TANK AND/OR LEACHING AREAS. ALL CHANGES MUST BE APPROVED BY THE DESIGN ENGINEER AND LOCAL HEALTH DEPARTMENT OFFICIALS.
11. LOT IS SERVED BY PRIVATE WELL.

ZONING DATA
ZONING DISTRICT: B-R3

	REQUIRED	PROVIDED
MAX. BUILDING HEIGHT	35'	35'
TENNIS COURT SETBACK FROM PROPERTY LINE	40 LF	42.3 LF
FROM STREETLINE	50 LF	322± LF
MAXIMUM BLDG. COVERAGE	10%	0.97%
MAXIMUM GROUND COVERAGE	30%	20.76%

REVISION

NO.	DATE	DESCRIPTION	DRAWN BY	CHECKED BY
1	3-26-21	Added landscaping, B100a septic design notes, S.A.L.	S.A.L.	M.E.L.

DYMAR
800 Main Street South · Southbury, CT 06488 · (800) 307-1066 · Fax (800) 307-1547
ENGINEERING · PLANNING · SURVEYING · DEVELOPMENT SERVICES

NOT FOR CONSTRUCTION


CLIENT: **Easton Racquet Club, Inc.**
36 Wimbledon Lane, P.O. Box 152
Easton, CT 06612

PROJECT: **Easton Racquet Club, Inc.**
36 Wimbledon Lane, P.O. Box 152
Easton, CT 06612

TITLE: **Site Development and Grading Plan**

DATE: 02/15/21
SCALE: 1"=40'
DESIGNED BY: M.E.L.
DRAWN BY: C.C.B.
CHECKED BY: M.E.L.
JOB NO: 00335
DRAWING NO: C-2

APPROVED BY EASTON PLANNING & ZONING COMMISSION
DATE: _____
SIGNED: _____
CHAIRMAN OR SECRETARY



PROPOSED PLANTING LIST

KEY	SPECIES	COMMON NAME	QUAN.	SIZE	SPAC.
ABI	ABIES CONCOLOR	WHITE FIR	12	6-7'	15' OC
AC	AMELANCHIER CANADENSIS	SHADBLow	3	#10 CNT	10' OC
CLA	CLETHRA ALNIFOLIA	SWEET PEPPERBUSH	8	3-4'	5' OC
IV	ILEX VERTICILLATA	WINTERBERRY	5	3-4'	5' OC
VL	VIBURNUM LENTAGO	NANNYBERRY	8	3-4'	5' OC

N/F BRIDGEPORT HYDRAULIC COMPANY

N/F BRIDGEPORT HYDRAULIC COMPANY

N/F BRIDGEPORT HYDRAULIC COMPANY


N/F ROBERT J. FIORE

N/F DALE E. & RONALD BEILIN

N/F RICHARD P. & MARY E. SABATINI


WIMBLEDON LANE

F:\03035\Civil\DWG\Title Ball Drawings\03035.dwg, Layout1, 4/12/2021 1:40:11 PM, gms, AutoCAD PDF (Web and Mobile) Plot, ARCT full bleed (24.00x 36.00 inches), 1:1



SUMMARY OF REGULATED ACTIVITIES								
R.I.A #	DESCRIPTION OF ACTIVITY	WETLAND AREA			100' WETLANDS SETBACK AREA (PROPOSED)		100' WETLANDS SETBACK AREA (TOTAL)	
		CUT(CY)	FILL(CY)	AREA(SF)	AREA(SF)	CUT(CY)	FILL(CY)	
1	PADDLE BOARD COURT #1	0	0	0	2,119	3	0	
2	PADDLE BOARD COURT #2	0	0	0	1,824	3	0	
3	PICKLEBALL COURTS, GRADING AND DRAINAGE	0	0	0	11,203	86	356	
REGULATED IMPACT AREA = R.I.A.		TOTALS	0	0	0	15,146	92	356
				0 AC	0.35 AC.			

N/F
BRIDGEPORT HYDRAULIC COMPANY



N/F
BRIDGEPORT
HYDRAULIC
COMPANY

N/F
RICHARD P. & MARY E. SABATINI

N/F
DALE E. & RONALD BEILIN

N/F
BRIDGEPORT
HYDRAULIC
COMPANY

N/F
ROBERT J. FIORE

- EXISTING DISTURBED WETLANDS SETBACK AREA
- PROPOSED DISTURBED WETLANDS SETBACK AREA
- PROPOSED CONSTRUCTION ACTIVITIES WITHIN EXISTING FACILITY AREAS

NO.	DATE	REVISION DESCRIPTION	DRAWN BY	CHECKED BY

DYMAR

800 Main Street South • Southbury, CT 06488 • Fax (203) 387-1547
ENGINEERING • PLANNING • SURVEYING • DEVELOPMENT SERVICES

DRAWINGS TO BE USED FOR LAND USE SUBMISSIONS ONLY
NOT FOR CONSTRUCTION

CLIENT: **Easton Racquet Club, Inc.**
36 Wimbledon Lane, P.O. Box 152
Easton, CT 06612

PROJECT: **Easton Racquet Club, Inc.**
36 Wimbledon Lane, P.O. Box 152
Easton, CT 06612

TITLE: **Wetlands Impact Plan**

DATE: 02/15/21
SCALE: 1"=40'
DESIGNED BY: M.F.L.
DRAWN BY: C.C.B.
CHECKED BY: M.F.L.
JOB NO: 00335
DRAWING NO: **C-3**

F:\0335\Civil\DWG\Title Ball Drawings\033.dwg, C-3, 4/1/2021 1:40:13 PM, gatus, AutoCAD PDF (Web and Mobile).pc3, ARCH full bleed D (24.00 x 36.00 inches), 1:1

TESTING PERFORMED BY DYMAR ON DECEMBER 3, 2005. EASTON RACQUET CLUB JOB #00335 -LOCAL HEALTH DEPARTMENT WAS PRESENT

TEST HOLE #1
 0" - 4" DARK BROWN TOP SOIL
 4" - 18" BROWN SANDY LOAM WITH TRACE GRAVEL AND TRACE COBBLES
 18" - 42" OLIVE BROWN VERY SILTY MEDIUM SAND WITH LITTLE TO SOME GRAVEL
 42" - 90" GREY BROWN MICA SCHIST WITH LITTLE GRAVEL AND TRACE COBBLES

ROOTS: 50"
 GROUNDWATER: 84"
 LEDGE: NONE
 MOTTLING: 26"
 COMMENTS: NONE

PERCOLATION TEST

DEPTH: 20"
 PRESOAK TIME: 12:45
 STARTING TIME: 13:45
TIME DEPTH
 0 MIN -
 5 MIN 0.87"
 10 MIN 0.90"
 15 MIN 0.92"
 20 MIN 0.94"
 25 MIN 0.96"
 30 MIN 0.98"
 40 MIN 1.02"
 50 MIN 1.05"
 60 MIN 1.08"

SEEPAGE RATE: 1" / 27' MIN

TEST HOLE #2

0" - 4" DARK BROWN TOP SOIL
 4" - 84" BROWN VERY SILTY FINE SAND WITH SOME GRAVEL, FEW COBBLES, AND FEW STONES

ROOTS: 54"
 GROUNDWATER: NONE
 LEDGE: NONE
 MOTTLING: NONE
 COMMENTS: AT 54" MICA IS PRESENT TO BOTTOM

PERCOLATION TEST

DEPTH: 24"
 PRESOAK TIME: 12:45
 STARTING TIME: 13:45
TIME DEPTH
 0 MIN -
 5 MIN 1.37"
 10 MIN 1.45"
 15 MIN 1.49"
 20 MIN 1.53"
 25 MIN 1.56"
 30 MIN 1.58"
 40 MIN 1.61"
 50 MIN 1.64"
 60 MIN 1.68"

SEEPAGE RATE: 1" / 40' MIN

TEST HOLE #3

0" - 2" DARK BROWN TOP SOIL
 2" - 60" LIGHT BROWN, VERY SILTY MEDIUM FINE SAND WITH LITTLE GRAVEL, FEW COBBLES, AND TRACE BOULDERS
 60" - 72" DARK BROWN LOAM
 72" - 90" DARK BROWN VERY SILTY MEDIUM FINE SAND WITH TRACE GRAVEL

ROOTS: 72"
 GROUNDWATER: NONE
 LEDGE: NONE
 MOTTLING: 58"
 COMMENTS: AREA SEEMS TO HAVE BEEN FILLED

TEST HOLE #4

0" - 4" DARK BROWN TOP SOIL
 4" - 84" BROWN VERY SILTY MEDIUM FINE SAND WITH SOME GRAVEL, SOME COBBLES, AND FEW STONES

ROOTS: 24"
 GROUNDWATER: NONE
 LEDGE: NONE
 MOTTLING: NONE
 COMMENTS: MICA ROCK STARTS AT 48"

PERCOLATION TEST

DEPTH: 30-32"
 PRESOAK TIME: 12:45
 STARTING TIME: 13:45
TIME DEPTH
 0 MIN -
 5 MIN 1.54"
 10 MIN 1.61"
 15 MIN 1.67"
 20 MIN 1.69"
 25 MIN 1.72"
 30 MIN 1.74"
 40 MIN 1.79"
 50 MIN 1.82"
 60 MIN 1.85"

SEEPAGE RATE: 1" / 27' MIN

TEST HOLE #5

0" - 4" DARK BROWN TOP SOIL
 4" - 26" LIGHT BROWN VERY SILTY FINE SAND WITH LITTLE GRAVEL
 26" - 36" VERY DARK BROWN SANDY LOAM
 36" - 84" DARK BROWN VERY SILTY FINE SAND WITH GRAVEL, FEW COBBLES, AND SOME STONES

ROOTS: NONE
 GROUNDWATER: NONE
 LEDGE: NONE
 MOTTLING: STAINING SPOTTY AT 36", STAINING APPEARS TO BE FROM RUNOFF FROM TENNIS COURTS, NOT FROM A HIGH GROUND WATER TABLE
 THIRD LAYER MAY BE FROM REMNANTS OF STOCKPILE AREA. (AREA APPEARS TO BE IN CUT FROM ORIGINAL GRADE)

PERCOLATION TEST

DEPTH: 40"
 PRESOAK TIME: 11:30
 STARTING TIME: 12:35
TIME DEPTH
 0 MIN -
 5 MIN 1.92"
 10 MIN 1.94"
 15 MIN 1.96"
 20 MIN 1.97"
 25 MIN 1.98"
 30 MIN 1.99"
 40 MIN 2.01"
 50 MIN 2.03"
 60 MIN 2.04"

SEEPAGE RATE: 1" / 60-80' MIN

TEST HOLE #6

0" - 3" DARK BROWN TOP SOIL
 3" - 36" DARK ORANGE BROWN SILTY FINE SAND AND GRAVEL WITH FEW COBBLES AND SOME STONES
 36" - 78" DARK OLIVE BROWN SILTY FINE SAND AND GRAVEL WITH FEW COBBLES AND SOME STONES

ROOTS: NONE
 GROUNDWATER: NONE
 LEDGE: NONE
 MOTTLING: STAINING SPOTTY AT 36", STAINING APPEARS TO BE FROM RUNOFF FROM TENNIS COURTS, NOT FROM A HIGH GROUND WATER TABLE
 COMMENTS: MANY NESTED ANGULAR COBBLES AND STONES IN BOTTOM LAYER

TEST HOLE #7

0" - 3" DARK BROWN TOP SOIL
 3" - 26" LIGHT BROWN VERY SILTY FINE SAND WITH LITTLE GRAVEL
 26" - 36" VERY DARK BROWN SANDY LOAM
 36" - 84" DARK BROWN VERY SILTY FINE SAND WITH GRAVEL, FEW COBBLES, AND SOME STONES

ROOTS: NONE
 GROUNDWATER: NONE
 LEDGE: NONE
 MOTTLING: STAINING AT 24" - 26"
 COMMENTS: STAINING APPEARS TO BE FROM RUNOFF FROM TENNIS COURTS, NOT FROM A HIGH GROUND WATER TABLE (AREA APPEARS TO BE IN CUT FROM ORIGINAL GRADE)

TEST HOLE #8

0" - 4" DARK BROWN TOP SOIL
 4" - 24" MEDIUM BROWN VERY SILTY MEDIUM SAND AND GRAVEL WITH FEW TO SOME COBBLES AND FEW TO SOME STONES
 24" - 30" ORANGE BROWN VERY SILTY MEDIUM SAND AND GRAVEL
 30" - 54" BROWN VERY SILTY MEDIUM SAND AND GRAVEL WITH SOME COBBLES
 54" - 78" TAN BROWN SILTY MEDIUM FINE SAND WITH TRACE GRAVEL AND TRACE COBBLES

ROOTS: NONE
 GROUNDWATER: NONE
 LEDGE: NONE
 MOTTLING: NONE
 COMMENTS: NONE

PERCOLATION TEST

DEPTH: 36"
 PRESOAK TIME: 11:30
 STARTING TIME: 12:35
TIME DEPTH
 0 MIN -
 5 MIN 1.99"
 10 MIN 2.05"
 15 MIN 2.08"
 20 MIN 2.10"
 25 MIN 2.12"
 30 MIN 2.13"
 40 MIN 2.15"
 50 MIN 2.17"
 60 MIN 2.19"

SEEPAGE RATE: 1" / 40' MIN

PERCOLATION TEST (3/29/02)

DEPTH: 30"
 PRESOAK TIME: 13:00
 STARTING TIME: 13:55
TIME DEPTH
 0 MIN 1.25"
 5 MIN 1.35"
 10 MIN 1.41"
 15 MIN 1.46"
 20 MIN 1.50"
 25 MIN 1.53"
 30 MIN 1.55"
 40 MIN 1.60"
 50 MIN 1.64"
 60 MIN 1.68"

SEEPAGE RATE: 1" / 20' MIN

TESTING PERFORMED BY DYMAR ON OCTOBER 23, 2020, MARCH 23, 2021 EASTON RACQUET CLUB JOB #00335

TEST HOLE #TH1 (PROPOSED PICKLEBALL COURT)

0" - 5" DARK BROWN TOPSOIL
 5" - 24" YELLOW BROWN LOAM, TRACE GRAVEL
 24" - 60" OLIVE BROWN VERY COMPACT SILTY GLACIAL TILL, WET

ROOTS: NONE
 GROUNDWATER: NONE
 LEDGE: NONE
 MOTTLING: 28", VERY STRONG
 COMMENTS: NONE

TEST HOLE #TH2 (PROPOSED PICKLEBALL COURT)

0" - 12" DARK BROWN FILL SUBSOIL WITH BOULDERS
 12" - 30" ORGANIC TOPSOIL, WET

ROOTS: NONE
 GROUNDWATER: NONE
 LEDGE: NONE
 MOTTLING: 12", STRONG

TEST HOLE #TH3 (PROPOSED PICKLEBALL COURT)

0" - 6" TOPSOIL
 6" - 48" GREY FINE SILTY LOAM WITH TRACE CLAY, TRACE GRAVEL, FILL

ROOTS: NONE
 GROUNDWATER: NONE
 LEDGE: NONE
 MOTTLING: 12", STRONG
 COMMENTS: NONE

TEST HOLE #201 (SANITARIAN PRESENT)

0" - 6" DARK BROWN TOPSOIL
 6" - 21" MISCELLANEOUS FILL
 21" - 37" LIGHT BROWN LOAM (ORIGINAL SOIL)
 37" - 80" OLIVE BROWN FINE TO MEDIUM SAND, TRACE SILT, TRACE GRAVEL, TRACE BOULDERS

ROOTS: 6"
 GROUNDWATER: 75"
 LEDGE: 80"
 MOTTLING: 24"

TEST HOLE #202 (SANITARIAN PRESENT)

0" - 9" DARK BROWN TOPSOIL
 9" - 27" MISCELLANEOUS FILL
 27" - 45" LIGHT BROWN LOAM (ORIGINAL SOIL)
 45" - 75" OLIVE BROWN FINE TO MEDIUM SAND, TRACE SILT, TRACE GRAVEL, TRACE BOULDERS

ROOTS: 9" (DENSE)
 GROUNDWATER: NONE
 LEDGE: 75"
 MOTTLING: 22"

SELECT FILL REQUIREMENTS:


- THESE SELECT FILL REQUIREMENTS SHALL MEET THE CONNECTICUT PUBLIC HEALTH CODE TECHNICAL STANDARDS FOR SUBSURFACE SEWAGE DISPOSAL SYSTEMS AS PUBLISHED JANUARY 2015 UNLESS NOTED OTHERWISE.
- THE FILL MATERIAL SHOULD NOT CONTAIN ANY MATERIAL LARGER THAN THREE (3) INCHES. A SIEVE ANALYSIS SHOULD BE PERFORMED ON A REPRESENTATIVE SAMPLE OF THE IN-PLACE FILL. IT IS RECOMMENDED THAT THE SYSTEM NOT BE INSTALLED UNTIL THE SEPTIC FILL HAS PASSED THE SIEVE TEST. UP TO 45% OF THE DRY WEIGHT OF THE FILL SAMPLE MAY BE RETAINED ON THE #4 SIEVE. THE MATERIAL THAT PASSES THE #4 SIEVE IS THEN DRIED AND REWEIGHED AND THE SIEVE ANALYSIS STARTED. THE SIEVE ANALYSIS MUST DEMONSTRATE THAT THE MATERIAL MEETS EACH OF THE FOLLOWING SPECIFICATIONS:

SIEVE SIZE	PERCENT PASSING BY WEIGHT WET SIEVE	PERCENT PASSING BY WEIGHT DRY SIEVE
#4	100	100
#10	70-100	70-100
#40	10-50*	10-75
#100	0-20	0-5
#200	0-5	0-2.5

* PERCENT PASSING THE #40 SIEVE CAN BE INCREASED TO NO GREATER THAN 75% IF THE PERCENT PASSING THE #100 SIEVE DOES NOT EXCEED 10% AND THE #200 SIEVE DOES NOT EXCEED 5%.
- FILL SHALL BE PLACED IN MAXIMUM LOOSE LIFT HEIGHTS OF TWELVE INCHES (12") AND TO BE COMPACTED TO 90%-95% MODIFIED OPTIMUM DRY DENSITY BY ASTM 1557 METHOD "C", UNTIL REQUIRED LEVEL IS OBTAINED. FIELD DENSITY TESTS SHALL BE CONDUCTED IN EACH LIFT IF REQUIRED BY THE HEALTH DEPARTMENT.
- THE SEQUENCE FOR THE PLACING OF FILL IS TO BE AS FOLLOWS:
 A. STRIP TOPSOIL WITHIN FILL LIMITS AND STOCKPILE OUTSIDE SEPTIC AREA FOR FUTURE USE. DO NOT STRIP TOPSOIL WITHIN 48 HOURS OF A RAIN STORM OR IF THERE ARE STANDING PUDDLES.
 B. EXCAVATE EXISTING MATERIAL TO DEPTHS AS SHOWN IN CROSS SECTION "A-A". CONTRACTOR TO CHECK ELEVATION OF SUBGRADE FOR REQUIRED SLOPES PRIOR TO PLACING SELECT FILL.
 C. FOLLOWING STRIPPING, THE STRIPPED SURFACE SHALL BE SCARIFIED WITH THE TEETH OF AN EXCAVATOR WORKING PARALLEL TO THE SURFACE TOPOGRAPHY.
 D. FILL SHALL BE DEPOSITED AT THE UPHILL EDGE OF THE LEACHING AREA AND PUSHED INTO THE SCARIFIED SURFACE. ANY DISTURBANCE TO THE SCARIFIED SURFACE SHALL REQUIRE RE-SCARIFICATION. FILLING AND COMPACTION SHOULD BE DISCONTINUED DURING RAIN STORMS AND FOR 24 HOURS THEREAFTER.
- AFTER ALL THE SELECT SEPTIC FILL HAS BEEN PLACED, THE DESIGN ENGINEER SHALL PERFORM A PERCOLATION TEST TO VERIFY THAT THE IN PLACE PERCOLATION RATE IS BETTER THAN OR EQUAL TO THE DESIGN RATE.

NOTES:

- THE CLUB SHALL MAINTAIN ITS CURRENT MEMBERSHIP AMOUNT OF 153 MEMBERS. ANY ADDITION TO THE MEMBERSHIP SHALL REQUIRE A RE-EVALUATION OF THE SEPTIC DESIGN.
- CONTRACTOR TO CONTACT TOWN INLAND WETLAND ENFORCEMENT OFFICER TO VERIFY ADDITIONAL EROSION CONTROL MEASURES TO PRIOR TO THE START OF WORK.
- EXCESS WATER USAGE DURING LARGE WEEKEND EVENTS WILL REQUIRE THE USE OF PORT-A-JOHNS.
- WATER METERS TO BE INSTALLED AT LOCATIONS APPROVED BY DYMAR AND MONITORED DURING THE SUMMER MONTHS.
- CONTRACTOR SHALL CONFIRM INVERT ELEVATIONS AT EXISTING POOL HOUSE PRIOR TO CONSTRUCTION. ENGINEER TO BE CONTACTED IF FIELD CONDITIONS REQUIRE DESIGN REVISIONS.



CONSTRUCTION SPECIFICATIONS & STANDARDS

A. MANHOLES, CATCH BASINS AND STRUCTURES:


- Refer to details.

B. STORM SEWER PIPES:

- All R.C.P. Storm Sewer Drainage Pipe specified shall be CLASS IV in streets and unimproved areas, except fifteen inch (15") catch basin laterals shall be CLASS V, or approved equal.
- All curtain drain pipe shall be 4", 6" or 8" (as specified on the drawings) perforated polyvinyl chloride plastic pipe (PVC) conforming to ASTM D 1785 with couplings and elbows shall conform to the requirements of ASTM D 2466 or D 2467. Class "I" heavy duty type, minimum slots 1/4" clear opening, except as otherwise shown on the plans. Pipe shall exit to a gravel lined drainage swale or drainage structure. All aggregate for underdrain shall be washed, size as specified.
- Pipe lengths for the storm drainage system are measured from centerline of structure to centerline of structure with the exception of flared ends which are measured from the outer most edge.
- Pipe inverts for storm drainage structures are measured at their centerline, while inverts for flared ends measured at their outer most edge.
- All piping shall be founded on a stone bedding in CLASS "B" and "C" trench installations for either earth or rock excavations, unless otherwise directed by the engineer. Refer to details.
- All pipe backfill shall be placed in compacted twelve inch (12") loose lifts to an AASHTO T-99 density of 95% to proposed subgrade.
- Pipes shall be cut flush to the inside walls of all structures. Openings at knockouts shall be mortared tight with a non-shrink grout. Concrete inverts and aprons shall be constructed to full pipe diameter of the existing or proposed pipe within manholes. Aprons shall slope to drain. Smaller pipe sizes entering structures shall, at a minimum, match the crown of the outgoing pipe, except as otherwise specified for critical elevations for upstream structures or in the case of significant grade changes.

NOTES:

- MINIMUM 12" OF COVER TO MEET H-10 LOADING, AND 24" OF COVER TO MEET H-20 LOADING.
- UNITS MUST BE BACKFILLED WITH CT DOT NO. 6 STONE AGGREGATE AS DEFINED IN THE CT PUBLIC HEALTH CODE.



NO.	DATE	DESCRIPTION	REVISION
1	3-26-21	Added test hole data and details.	


DYMAR
 800 Main Street South · Southbury, CT 06488 · (803) 287-1046 · Fax (803) 287-1847
 ENGINEERING · PLANNING · SURVEYING · DEVELOPMENT SERVICES

CLIENT: Easton Racquet Club, Inc.
 36 Wimbeldon Lane, P.O. Box 152
 Easton, CT 06612
 PROJECT: Easton Racquet Club, Inc.
 36 Wimbeldon Lane, P.O. Box 152
 Easton, CT 06612
 TITLE: Construction Specifications & Standards and Test Hole Data and Septic Details

DATE:	02/15/21
SCALE:	N.T.S.
DESIGNED BY:	M.E.L.
DRAWN BY:	C.C.B.
CHECKED BY:	M.E.L.
JOB NO.:	00335
DRAWING NO.:	C-4

NOTE:
 1. THE CONTRACTOR SHALL NOTIFY "CALL BEFORE YOU DIG" AT LEAST 72 HOURS PRIOR TO THE START OF EXCAVATION, BY CALLING 1-800-922-4435.

C-4




EROSION & SEDIMENTATION CONTROL LEGEND

ABBREVIATIONS:
 LS - LEVEL SPREADER
 TSP - TEMPORARY SOIL PROTECTION
 TRM - TURF REINFORCEMENT MAT
 SSP - STONE SLOPE PROTECTION
 WCFM - WOOD CELLULOSE FIBER MULCH
 W/TACKIFIER
 ECB - EROSION CONTROL BLANKET

KEY		
(GSF)	SILT FENCE	
(CE)	ANTI-TRACKING PAD	
(HB)	HAY BALES	
(SW)	STRAW WADDLE BARRIER	
(IP)	DRAIN INLET SILTSACK TRAP	
(WB)	WATER BREAK	
(TS)	TEMPORARY SWALE	
(PS)	PERMANENT SWALE	
(SCD)	STONE CHECK DAM	
(HCD)	HAY BALE CHECK DAM	
(SS)	SLOPE SOIL STABILIZATION	
(SA)	STOCKPILE AREA	
(MTA)	MATERIAL STAGING AREA	
(OP)	RIPRAP OUTLET SPLASH PAD	
(LS)	PLUNGE POOL	
(SB)	SEDIMENTATION/STILLING BASIN	
(TST)	SEDIMENTATION TRAP	
(TP)	TREE PROTECTION	

NOTE:
 1. KEY BASED ON 2002 CT EROSION & SEDIMENTATION CONTROL GUIDELINES. IF MARKED BY *, NOT FOUND IN BOOK.
 2. TREES WITHIN CLEAR LIMIT TO BE REMOVED - NOT ALL SHOWN PER LEGEND. THOSE 'X' OUT ARE ALONG PERIMETER (TYP.).



NOTE:
 1. THE CONTRACTOR SHALL NOTIFY "CALL BEFORE YOU DIG" AT LEAST 72 HOURS PRIOR TO THE START OF EXCAVATION, BY CALLING 1-800-922-4455.

NO.	DATE	REVISION	DESCRIPTION	DRAWN BY	CHECKED BY
1	3-26-21		Revised Erosion Control limits.	S.A.L.	M.E.L.

DYMAR

800 Main Street South · Southbury, CT 06488 · (803) 387-1066 · Fax (803) 387-1547
 ENGINEERING · PLANNING · SURVEYING · DEVELOPMENT SERVICES

DRAWINGS TO BE USED FOR LAND USE SUBMISSIONS ONLY
 NOT FOR CONSTRUCTION

MATCH LINE - SEE SHEET C-4B

CLIENT: **Easton Racquet Club, Inc.**
 36 Wimbeldon Lane, P.O. Box 152
 Easton, CT 06612

PROJECT: **Easton Racquet Club, Inc.**
 36 Wimbeldon Lane, P.O. Box 152
 Easton, CT 06612


TITLE: **Sediment & Erosion Control Plan**

DATE:	02/15/21
SCALE:	1"=20'
DESIGNED BY:	M.E.L.
DRAWN BY:	C.C.B.
CHECKED BY:	M.E.L.
JOB NO:	003335
DRAWING NO:	C-5A

F:\0335\Civil\DWG\Title Ball Drawings\0335-Arch.dwg, A, 4/12/2021 1:40:17 PM, gatus, AutoCAD PDF (Wide and Mobile) pset, ARCH Full bleed D (24.00 x 36.00 inches), 1:1

F:\03035\Civil\DWG\Title_Bal Drawings\03035-Ang_B_412021 1:40:17 PM, gatus, AutoCAD PDF (Web and Mobile).pc3, ARCH Full bleed D (24.00 x 36.00 inches), 1:1

MATCH LINE - SEE SHEET C-5A



EROSION & SEDIMENTATION CONTROL LEGEND

ABBREVIATIONS:
 LS - LEVEL SPREADER
 TSP - TEMPORARY SOIL PROTECTION
 TRM - TURF REINFORCEMENT MAT
 SSP - STONE SLOPE PROTECTION
 WCFM - WOOD CELLULOSE FIBER MULCH
 W/TACKIFIER
 ECB - EROSION CONTROL BLANKET

KEY	DESCRIPTION	SYMBOL
GSF	SILT FENCE	***
CE	ANTI-TRACKING PAD	▨
HB	HAY BALES	---
SW	STRAW WADDLE BARRIER	▨
IP	DRAIN INLET SILTSACK TRAP	□
WB	WATER BREAK	▨
TS	TEMPORARY SWALE	>>>>
PS	PERMANENT SWALE	>>>>
SCD	STONE CHECK DAM	⊥
HCD	HAY BALE CHECK DAM	⊥
SS	SLOPE SOIL STABILIZATION	▨
SA	STOCKPILE AREA	▨
MTA	MATERIAL STAGING AREA	▨
OP	RIPRAP OUTLET SPLASH PAD	⊥
LS	PLUNGE POOL	⊥
SB	SEDIMENTATION/STILLING BASIN	⊥
TST	SEDIMENTATION TRAP	⊥
TP	TREE PROTECTION	○

NOTE:
 1. KEY BASED ON 2002 CT EROSION & SEDIMENTATION CONTROL GUIDELINES. IF MARKED BY *, NOT FOUND IN BOOK.
 2. TREES WITHIN CLEAR LIMIT TO BE REMOVED - NOT ALL SHOWN PER LEGEND. THOSE 'X' OUT ARE ALONG PERIMETER (TYP.).

NO.	DATE	REVISION	DESCRIPTION	DRAWN BY	CHECKED BY
1	3-26-21		Revised Erosion Control limits.	S.A.L.	M.E.L.

DYMAR

800 Main Street South · Southbury, Ct. 06488 · Fax (803) 307-1547
 ENGINEERING · PLANNING · SURVEYING · DEVELOPMENT SERVICES

NOT FOR CONSTRUCTION

CLIENT:	Easton Racquet Club, Inc. 36 Wimbeldon Lane, P.O. Box 152 Easton, CT 06612
PROJECT:	Easton Racquet Club, Inc. 36 Wimbeldon Lane, P.O. Box 152 Easton, CT 06612
TITLE:	Sediment & Erosion Control Plan
DATE:	02/15/21
SCALE:	1"=20'
DESIGNED BY:	M.E.L.
DRAWN BY:	C.C.B.
CHECKED BY:	M.E.L.
JOB NO.:	00335
DRAWING NO.:	C-5B

NOTE:
 1. THE CONTRACTOR SHALL NOTIFY "CALL BEFORE YOU DIG" AT LEAST 72 HOURS PRIOR TO THE START OF EXCAVATION, BY CALLING 1-800-922-4455.

EROSION & SEDIMENT CONTROL PLAN

A. PROJECT NARRATIVE:

- The project is an expansion of a recreational tennis club situated upon 10± acres. The expansion has been designed in accordance with the Town's inland wetlands and watercourses regulations and zoning regulations as well as other documents published by the CT Department of Energy and Environmental Protection and the CT Department of Transportation.
- There is no Open Space proposed with this project.
- The infrastructure proposed includes the construction of two illuminated paddle board courts with the appropriate walkway and stairs for access, an illuminated pickleball, upgrade the illumination of the existing tennis courts, extend the sidewalk to the proposed pickleball court. The project also calls for the demolition of the practice court and a removal and relocation of the playground area.
- All work to be done in one phase.
- Regulated wetland activities – Refer to Sheet C-3.
- Total Estimated Additional Site Disturbance is 0.35± ac.
- Sequence of Construction Phasing Schedule – Refer to Section 'D' of this sheet for General Terms and practices for Erosion and Sediment Control measures.
- Reference is made to Sheets C-5D for the use of temporary Erosion and Sediment Control devices, their design criteria, and maintenance thereof.

B. PRINCIPLES:

The following general principles shall be maintained as an effective means of minimizing erosion and sedimentation during the development process.

- Stripping away of vegetation, regrading or other development shall be done in such a way as to minimize erosion.
- Grading and development plans shall preserve salient natural features, keep cut and fill operations to a minimum, and insure conformity with topography so as to create the least erosion potential and adequately handle the volume and velocity of surface water runoff.
- Whenever feasible, natural vegetation shall be retained, protected and supplemented wherever indicated on the site development plan and/or the landscaping plan. Trees which are shown to remain shall be protected throughout the construction period and any damages caused by the CONTRACTOR shall be repaired immediately. Whenever trees are cut beyond the contract limit lines or if a tree cannot be saved due to the CONTRACTOR'S actions, due compensation shall be granted to the OWNER equal to or exceeding the value of the loss. No work shall proceed after damages have occurred until the OWNER has agreed to a remediation plan.
- The disturbed area and the duration of exposure shall be kept to a practical minimum.
- Disturbed soils shall be stabilized as quickly as possible.
- Temporary vegetation and/or mulching shall be used to protect exposed critical areas and stockpiles during development when expected to be exposed in excess of fifteen (15) days.
- The permanent (final) vegetation and mechanical erosion control measures shall be installed as soon as practical during construction.
- Sediment in the runoff water shall be trapped until the disturbed areas are stabilized by the use of debris basins, sediment basins, silt traps or similar measures.
- All lots, tracts or developments shall be finally graded to provide proper drainage away from buildings and dispose of it without ponding; and all land within a development shall be graded to drain and dispose of surface water without ponding.
- Where drainage swales are used to divert surface waters away from buildings, they shall be sodded or planted.
- Concentration of surface runoff shall be only permitted by piping and through drainage swales reinforced with structural protective measures or natural watercourses.
- Excavation and Fills:
 - Slopes created by cuts or fills shall not be steeper than 2:1 unless existing soil conditions are impacted stabilized and shall be reestablished by temporary or permanent measures, as required during the development process.
 - Adequate provisions shall be made to prevent surface water from damaging the cut face of excavations or the sloping surfaces of fills.
 - Cut and fills shall not endanger adjoining property.
 - All fills shall be compacted to provide stability of material and to prevent undesirable settlement. The fill shall be spread in a series of layers each not exceeding loose lifts of twelve (12) inches in thickness and shall be compacted by a sheeps foot roller or other approved method after each layer is spread.
 - Fills shall not encroach on natural watercourses, constructed channels or regulated flood plain areas, unless permitted by license or permit from authority having jurisdiction.
 - Fills placed adjacent to natural watercourses, constructed channels or flood plains shall have suitable protection against erosion during periods of flooding.
 - Grading shall not be done in such a way as to divert water onto the property of another landowner without their expressed written consent.
 - During grading operations, necessary measures for dust control shall be exercised. Use of chemicals shall be prohibited.

- Sedimentation and erosion control shall be implemented in accordance with the guidelines for Soil Erosion and Sediment Control, prepared by the State of Connecticut thru the counsel on Soil and Water Conservation, latest revised edition. In addition to defining specific measures and locations for sediment and erosion controls to be used, the plan shall be considered flexible to allow additional controls to be implemented as site conditions change and localized drainage patterns are altered. It is the responsibility of the CONTRACTOR to contact the OWNER for remedial action when site conditions warrant additional protective measures.

C. RESPONSIBILITY FOR THE PLAN:

- The responsibility for implementing and maintaining the Sedimentation and Erosion Control Plan rests with the OWNER OF RECORD where any development of the parcel gives cause to erosion and sedimentation. It is also to be said that the OWNER OF RECORD shall be held responsible for informing all concerned regarding responsibility of the plan and seeing that the plan becomes a part of the deed in the event the title of the property is transferred. The costs of all drainage erosion and sedimentation control measures will therefore rest with the OWNER OF RECORD.
- Whenever sedimentation is caused by stripping vegetation and/or grading, it shall be the responsibility of the person, corporation or other entity having responsibility to remove sedimentation from all lower properties, drainage systems and watercourses and to repair any damage at their expense as quickly as possible.
- Maintenance of all drainage facilities and watercourses within any subdivision or land development shall be the responsibility of the OWNER OF RECORD until they are accepted by the Municipality. All control measures will be maintained in effective condition throughout the construction period. Surface inlets shall be kept open and free of sediment and debris. The system shall be checked after every major storm and sediment shall be disposed of at an approved location consistent with the plan.
- Maintenance of drainage facilities or watercourses originating and completely on private property shall be the responsibility of the OWNER to their point of open discharge at the property line or at a communal watercourse within the property.
- No person, corporation or other entity shall block, impede the flow of, alter, construct any structure or deposit any material or thing or commit any act which affects normal or flood flow in any communal stream or watercourse without having obtained prior approval from the Canton Inland Wetland and Watercourse Agency.
- An adequate right-of-way and/or easement shall be provided for all drainage facilities and watercourses which are proposed either for acceptance by the Municipality or provided by other property owners for the convenience of the OWNER.

D. SEQUENCE OF CONSTRUCTION (GENERAL TERMS)

The tentative sequence of construction events are as follows and activities noted by a "(Capital Letter)" may occur concurrently.

- Conduct a preconstruction meeting with the OWNER, Contractor, Consultant Team, and Local and State agencies having jurisdiction over the project.
- Field stakeout the limits of all activities and install, at a minimum, a snow fence along construction limit lines along environmentally sensitive and tree protection areas. Silt fencing may be substituted where it coincides with this line, but only as approved by the OWNER. (A)
- Install silt fence along all sides contiguous to wetlands, watercourses and property owned by others affected by the work. Refer to Sedimentation and Erosion Control Plans for locations. (A)
- After each rain storm monitor the sedimentation and erosion control structures, which may include riprap channels, sediment basins, plunge pools, etc. Routinely remove sediment during construction to an approved site location when controls exceed one half (1/2) their capacity. (A)
- Clear vegetation within project limits, except trees designated to remain or in question, as shown on the plans. The decision of how questionable trees are to be treated shall rest with the OWNER and coordinated through the local agency having jurisdiction as construction progresses. All trees and shrubs less than 6" in diameter, and not to remain, shall be chipped and stored on site for mulch. (A)
- Remove stumps and dispose of at a bulky waste site approved by the ENGINEER and local official having jurisdiction. Disposal of stumps within burial pits on-site shall be prohibited. (B)
- Install a six inch (6") deep crushed stone anti-tracking pad, detailed and dimensioned on the drawings. At the end of each working day or as required, accumulated soil is to be swept from existing pavement. (B)
- Strip topsoil and subsoil materials as required and stockpile them at locations as shown on the Sedimentation and Erosion Control Plans. Stockpiles may be relocated to meet job conditions but shall not adversely impact any down gradient wetlands. Locations are subject to the ENGINEER'S approval. Provide temporary erosion controls on the downside slopes of all stockpiles. (B)
- Install drainage, retention basins, sediment traps, riprap swales, and other structural controls as necessary to capture and minimize sediment migration. (C)
- Conduct all rough cuts and fills for courts, utilities, and landscaped areas, making sure that all fill material is free of brush, rubbish, large boulders, logs, stumps and other objectionable materials. (C)
- If blasting is required for any cuts, all proposed work is to be coordinated with all local officials having jurisdiction. The contractor is required to secure all permits for blasting operations in accordance with local and state regulations and conduct a pre-blast survey of surrounding properties. Rock spoil is to be disposed of in an appropriate manner as the site plan may show or as locally permitted. (C)
- Provide temporary seeding measures on all exposed soil which were damaged due to construction activities, are outside of construction traffic zones, and are not to be permanently restored or for a period in excess of thirty (30) days. Seeding and seedbed preparation are as specified herein or as indicated on the landscape plan. (C)
- Excavate and complete remaining drainage. Install silt sack sediment barriers at all catch basins locations. (D)
- Complete final subgrading for all grassed and landscaped areas. Prepare subgrades for placing a minimum of six inches of topsoil. Place topsoil only when permanent seeding and landscaping can follow within a reasonable time frame (E).
- Exercise final landscaping plan and permanent seeding to provide long-term stabilization (E).
- Clean and remove all silt from within drainage structures and dispose of materials at an approved site (F).
- Remove temporary measures once permanent measures have matured as approved by the Municipality's enforcement officer (F).
- Conduct final inspection with Town to identify deficiencies and establish punch list; complete same to the satisfaction of the Town.

E. SEEDING AND PLANTING REQUIREMENTS:

- Seedbed Preparation: Fine grade and rake surface to remove stones larger than 2" in diameter. Install needed erosion control devices such as surface water diversions. Grade stabilization structures, sediment basins or drainage channels to maintain grassed areas. Apply limestone at a rate of 90 lbs / 1000 sft unless otherwise required according to soil test results. Apply 10-10-10 fertilizer at a rate of 7.5 lbs / 1000 sft. Work lime and fertilizer into soil uniformly before seeding.
- Seed Application: Apply grass mixtures at rates specified by hand, cyclone seeder or hydroseeder. Increase seed mixture by 10% if hydroseeder is used. Lightly drag or roll the seeded surface to cover seed. Seeding for selected fine grasses should be done between April 1 and June 1 or between August 15 and October 15. If seeding cannot be done during these times, repeat mulching procedure below until seeding can take place or seed with a quick germinating seed mixture to stabilize slopes. A quick germinating seed mixture (Domestic Rye) can be applied between June 15 and August 15 as approved by the LANDSCAPE ARCHITECT or ENGINEER.

- Mulching: Immediately following seeding, mulch the seeded surface with straw, hay or wood fiber at a rate of 1.5 to 2 tons / Ac. except as otherwise specified elsewhere. Mulches should be free of weeds and coarse matter. Temporary mulches shall be anchored down on slopes in excess of 3% and within channels of concentrated flows.

Gross Seed Mixtures:

Temporary Covers

Perennial Rye Grass . 20 lbs / Ac. Creeping Red Fescue .20 lbs / Ac.
Annual Rye Grass . . 20 lbs / Ac. Canada Bluegrass . . .20 lbs / Ac.

Permanent Covers

Substitutions equal to or better than that specified may be permitted based on the local availability of seed mixtures and seasonal conditions when approved by the LANDSCAPE ARCHITECT or ENGINEER.


Planting Notes:

- All materials shall be inspected, approved and site located by the LANDSCAPE ARCHITECT or ENVIRONMENTAL SUPERVISOR. All plant materials are to be inspected for defects or damage before planting. Substandard materials shall be returned to and replaced by the CONTRACTOR. Acceptable plants are to be planted per the specifications of the landscaping plan. It is the responsibility of the GENERAL CONTRACTOR to provide for the safekeeping and maintenance of plants and vegetation cover for the duration of site construction activity. Once planted, all machinery shall avoid planted areas which should be demarcated clearly by flagged field stakes. Provisions for regular watering and inspections shall be made by the NURSERY CONTRACTOR for the duration of the plant's first year in the ground and all plants which do not survive shall be replaced at the CONTRACTOR'S expense.
- All plant material placement is subject to field adjustment in response to other site conditions. These adjustments shall be at the discretion of the ARCHITECT, LANDSCAPE ARCHITECT, SITE SUPERVISOR or ENVIRONMENTALIST.
- All plant materials are subject to replacement by suitable alternatives per agreement between OWNER, LANDSCAPE ARCHITECT or ENGINEER, NURSERY CONTRACTOR and appropriate agencies.

F. REGULATORY COMPLIANCE

- The OWNER of record or its agent shall be responsible for registering the project with the CTDEP for "Discharge of Stormwater and Dewatering Wastewaters" per Section 22a-430b of the Connecticut General Statutes whenever five acres or more of accumulated disturbance will occur with the parcel's boundaries.
- The OWNER of record shall be responsible for retaining a licensed Professional Engineer or Certified Soil Erosion & Sediment Control Specialist to inspect the site periodically in accordance with CTDEP guidelines. Monitoring reports shall be prepared and filed with the OWNER, contractor and Inland-Wetland office of the Town.

The Applicant shall be responsible for obtaining all local permits and approvals required from the Planning Commission, including Wetlands and Watercourses' Commission and any necessary agencies and departments to satisfy the regulations of the Town.



NOTE:
1. THE CONTRACTOR SHALL NOTIFY "CALL BEFORE YOU DIG" AT LEAST 72 HOURS PRIOR TO THE START OF EXCAVATION, BY CALLING 1-800-922-4455.

NO.	DATE	DESCRIPTION	DRAWN BY	CHECKED BY
1	3-26-21	Added Coir Log Detail.	S.A.L.	M.E.L.

DYMAR

800 Main Street South · Southbury, Ct 06488 · (800) 367-1066 · Fax (800) 367-1547
ENGINEERING · PLANNING · SURVEYING · DEVELOPMENT SERVICES

NOT FOR CONSTRUCTION

CLIENT: **Easton Racquet Club, Inc.**
36 Wimbeldon Lane, P.O. Box 152
Easton, CT 06612

PROJECT: **Easton Racquet Club, Inc.**
36 Wimbeldon Lane, P.O. Box 152
Easton, CT 06612

TITLE: **Sediment & Erosion Control Narrative**

DATE: 02/15/21
SCALE: N.T.S.
DESIGNED BY: M.E.L.
DRAWN BY: C.C.B.
CHECKED BY: M.E.L.
JOB NO: 003335
DRAWING NO: **C-5C**

F:\030335\Civil\DWG\Public Ball Drawings\030335.dwg, Sec. 4/1/2021 1:40:19 PM, gsmis, AutoCAD PDF (Web and Mobile).pc3, ARCHFull.treed (0,00,00 inches), 1:1

SEDIMENT & EROSION CONTROL CONSTRUCTION STANDARDS:

A. PREAMBLE

The management goals of controlling anticipated impacts to surficial bedrock and soils during and immediately after construction are to reduce the transport and deposition of exposed surficial materials to wetlands and watercourses. A comprehensive erosion control plan has been prepared for the project utilizing both temporary and permanent devices to minimize impacts. The plan includes limitations of the duration of soil exposure, criteria and specifications for placement and installation of erosion control devices, a maintenance schedule, and enforcement suggestions to mitigate concerns over its implementation. The primary aim of the erosion and sedimentation control measures will be to reduce soil erosion from areas stripped of vegetation during construction and to prevent siltation of the wetland areas. The erosion and sedimentation control plans are based on the Connecticut Department of Environmental Guidelines and that of the General Permit for Stormwater Protection Discharges.

B. OBJECTIVES AND PRINCIPLES

The objectives of the Soil Erosion and Sediment Control Plan are to manage both runoff and the earthwork operations by utilizing a collective approach to managing their impacts before critical areas are affected. These objectives are as follows:

- Control erosion at its source with temporary control structures, minimize the runoff from areas of disturbance, and deconcentrate and distribute stormwater runoff through natural vegetation before discharge to critical zones such as streams or wetlands.
- Keep land disturbances to a minimum – The road alignments and building sites have been located with consideration given to the natural topography and the soil type. This design approach minimizes the required earthwork, thereby lowering the erosion potential.
- Time grading and construction to minimize soil exposure – The development will be phased to minimize the extent of cleared soil at any particular time. Within the scheduled phasing, only areas under active construction will be exposed. Residential lots, for example, will remain undisturbed until actual construction of the house is to begin.
- Retain existing vegetation wherever feasible – Silt fencing will be used to physically define the limit of work. Substantial buffers of existing vegetation will be provided along the proposed public ways.
- Stabilize disturbed areas as soon as possible – In areas where work will not occur for periods longer than two weeks, soil stabilization by hydroseeding or mulching will be done within 48 hours after the land has been cleared.
- Minimize the length and steepness of slopes – The project has engineered the steepness and length of slopes to minimize runoff velocities and to control concentrated flow. Where concentrated (swale) flow from exposed surfaces is expected to be greater than three feet per second, hay bale or stone check dams will be installed in the swale. The check dams will be placed so that unchecked flow lengths will not be greater than 100 feet.
- Maintain low runoff velocities – To protect disturbed areas from stormwater runoff, hay bale and/or soil diversion berms will be installed wherever runoff is likely to traverse newly exposed soil. Immediately following the clearing and stripping of topsoil, rough grading for the post-construction swales will take place. The swales will direct runoff so that it can be checked or impounded. Stormwater outlets will be designed to reduce velocities and dissipate energy.
- Trap sediment on-site and prior to reaching critical areas such as wetlands – Silt fences, hay bale check dams, filter strips, sediment traps, and catch basin filters will be used to either impound sediment-laden runoff or to filter the runoff as it flows through an area. Reference is made to the sedimentation and erosion control drawings, sheets C-6A through C-6F for location of silt fences, hay bales, etc. Silt fencing, augmented by hay bale berms installed on the upgradient side of the silt fencing, will be used wherever land disturbance occurs within 100 feet of wetlands. Stabilized construction entrances will be installed at all construction entrances to prevent construction vehicles from tracking sediment onto off-site roadways. All temporary erosion control devices will be installed prior to the commencement of construction.
- Establish a thorough maintenance and repair program – Erosion control measures will be inspected weekly during the spring months, monthly during the dry summer months and/or following rainfall storms of greater than 1/2 inch, and repaired as needed to ensure that they function properly.
- Assign responsibility for the maintenance program – The responsibility for the maintenance program will be assigned to the contractor who shall designate one of its supervisory personnel to be the liaison to the Owner's representative. The Owner will retain the services of a licensed professional who shall inspect and monitor the contractor's methods and have the authority to require modifications to the E&S controls. The Town will be copied on all inspection reports prepared on behalf of the project.

C. TEMPORARY E&S CONTROL DEVICES, DESIGN CRITERIA, AND MAINTENANCE

The devices provided below are typical controls which may or may not be required for the site. However, when site conditions arise which the Engineer, Site Monitor or Town warrant are necessary, the Contractor is to follow the guidelines specified as follows.

- Silt Fences** – Silt fences consist of wire-bound woodroll snow fence covered with a filter fabric. The fence will be four feet high and made of 3/8-inch by 1 1/2-inch wide pickets, approximately two inches apart, bound together by 13-gauge galvanized steel wire. Fences will be secured in place by galvanized steel posts set a maximum of five feet on-center. The filter fabric will be stapled to the upgradient face of each fence. Twine will be used to secure the fence on the uphill side to prevent overturning. The purpose of silt fences is to intercept and detain sediment contained in overland runoff from disturbed areas of limited extent. In addition, the silt fencing will physically delineate the limit of work. (Eirvine by Mirafi, Inc., is an acceptable alternative to the above described system).
- Installation and Maintenance:**
 - Silt fences will be installed where the disturbed land is located 200 feet or less from critical areas (streams and wetlands).
 - Silt fences will be installed on downslope of work areas as close to the disturbed areas as possible.
 - At the base of drainageways or where the disturbance will remove natural vegetation within 100 feet of critical areas, the silt fencing will be augmented by a single row of staked haybales.

- Filter fabric will be Trevira 1127.
 - Sediment will be removed from behind siltation fences when sediment has accumulated to 25% of original height of the fence.
- Hay Bale Diversion Berm** – Hay bale diversion berms will be utilized to intercept sediment and reduce runoff velocities around stockpiled earth materials and divert runoff away from disturbed areas of limited extent. This device will be used both upgradient/downgradient of grading operations.

Installation and Maintenance:

- The contributory drainage area will be one acre or less; the area may be larger if inaccessible to construction equipment and to preserve existing trees and vegetation.
 - The bales will be tightly bound, pin anchored, and imbedded four inches below grade, with ends tightly abutting each other.
 - The hay bale berms shall be inspected periodically and deteriorated bales replaced until such time as construction is completed and exposed slopes have been stabilized.
- Hydroseeding** – Hydroseeding will be the primary means of stabilizing areas of disturbed earth. Hydroseeding will not be permitted, however, within cut areas or steep slopes. The seed mix, fertilizer, water, and mulch will be applied as a mixture utilizing power equipment. Fertilizer will not be included in the mix for disturbance within the regulated area adjacent to wetlands. The mix will be applied in two equal applications. Dyes will be used to determine the extent of coverage upon application. After grass has appeared, those areas which fail to show a uniform stand of grass will be reseeded. This process will be repeated until all areas are covered with satisfactory growth. Hydroseeding will be completed within 48 hours following completion of rough grading. Seed mixtures appropriate to the soils, slopes and uses will be selected in accordance with the Westchester County Soil and Water Conservation District Guidelines.
 - Erosion Control Blankets** – Blankets will be utilized for slopes > 4:1 to stabilize areas of disturbed earth. The type of blanket shall be as manufactured by North American Green or approved equal in accordance with the following schedule:
 - For slopes from 4:1 to 3:1 and low flow swales use S75 Straw Blankets.
 - For slopes from 3:1 to 2:1 and moderate flow swales use S150 Straw Blankets.
 - For slopes from 2:1 to 1:1 and discharge grass channels use SC150 Coconut Fiber and Straw Blankets.
 - For slopes steeper than 1:1 and engineered channels use C125 Coconut Fiber Blankets.

Install all blankets in accordance with all the manufactures recommendations.

- Dust Control** – Water will be applied by sprinkler or water truck as necessary during grading operations to minimize sediment transport and maintain acceptable air quality conditions. Repetitive treatments will be done as needed until grades are paved.
- Stabilized Construction Entrance** – A ramp of crushed stone extending a minimum distance of 100 feet will be installed at each point of ingress and egress to the site. The purpose of the device is to minimize the potential of tracking mud from the site onto public rights-of-way.

Installation and Maintenance:

- Minimum length will be 100 feet
 - Stone size will be 1.5 to 2.5 inches
 - Stone will be placed upon the full width of the entrance roads
 - Thickness of stone will be six inches or greater
 - Additions of stone will be done periodically to maintain the entrance
 - All sediment spilled, dropped, washed, or tracked onto public rights-of-way will be removed immediately.
- Roadway Interceptor Swales** – This temporary device consists of a crushed stone-filled swale constructed across proposed roadways. The purpose of this device is to direct runoff away from the road surface and minimize sediment from entering the drainage system. This shortens the length of disturbed slope by intercepting runoff and diverting it away from the roadway catch basins.

Installation:

- Swales will be placed across roads, which are to be constructed in fill:
 - every 200 feet on slopes of five to ten percent, and
 - every 300 feet on slopes less than five percent.
 - Contributory drainage area less than five acres.
 - Swales drain to sediment traps or sedimentation basins.
- Hay Bale Check Dams** – Hay bale check dams consist of tightly bound, steel pin anchored hay bales embedded four inches below grade in drainage swales adjacent to roadways or against diversion berms at the toe of an exposed slope. The purpose of a hay bale check dam is to reduce runoff velocity and promote deposition and filtering of sediment from runoff.

Installation and Maintenance:

- Check dams will be placed in drainage swales or against diversion berms at the toe of an exposed slope:
 - every 100 feet on slopes greater than ten percent,
 - every 200 feet on slopes of five to ten percent, and
 - every 300 feet on slopes less than five percent.
- Sediment shall be removed from hay bale check dams when sediment has accumulated to 50 percent of the original height.

Installation and Maintenance:

- Contributory drainage areas less than or equal to five acres.

- Utilized as part of swales prior to discharge to natural slopes.
 - Traps will be placed such that runoff discharging from the trap will flow at least 30 feet overland through natural vegetation before entering stream channels or wetlands.
 - Traps will be designed for a minimum of 1.9 cubic feet of storage/acre of drainage area received by the trap.
 - Maximum depth of trap will be five feet.
 - Trap embankments shall not exceed five feet in height. Top width shall be four feet and sides shall have a 2:1 or flatter slope.
 - Trap sides shall be compacted during construction.
 - The trap outlet shall have crushed stone rip-rap hand placed over the trap.
 - Traps will be cleaned when sediment has accumulated to 50 percent of design volume and removed sediment deposited so it will not erode.
- Diversion/Interceptor** – Both grassed swales and rock-lined swales will be utilized (depending on grade) to convey runoff during construction. Swales generally will be located adjacent to roads. At frequent intervals, runoff in the roadway swales will pass through hay bale check dams and sediment traps to reduce velocities and remove sediment. As often as possible, runoff in the swales will be directed overland and allowed to filter through natural vegetation.

Installation:

- Grassed swales on slopes less than five percent.
- Rock-lined swales on slopes greater than five percent.
- Swales will be temporary.

- Catch Basin Filters** – Temporary catch basin filters will be utilized to prevent the deposition of sediment into the storm sewer system prior to the stabilization of exposed areas with vegetation and/or pavement. These filters will consist of tightly bound, pin-anchored hay bales embedded four inches below grade, surrounding each catch basin inlet.

Installation and Maintenance:

- Placed around each catch basin inlet prior to paving or stabilization with vegetation.
- Sediment shall be removed from the filters when it has accumulated to 50 percent of the filter's original height.

- Diversion Berm (Soil)** – This is a temporary raised berm of compacted soil, placed across a disturbed slope, that intercepts runoff from disturbed areas and directs it to an appropriate outlet. This device will be used mostly on steep slopes above deep excavations.

Installation:

- Diversion berms may be placed on cut and fill slopes exceeding ten feet in height.
- Contributory drainage area should not be greater than one acre.
- Runoff will be diverted overland by the berms to sediment traps, sedimentation basins, swales, or check dams.
- On slopes over five percent, additional stabilization is required in the form of stone rip-rap eight inches vertically along the upslope side of the berm and seven feet upslope from the upslope toe of the berm.
- Top width of berm will be two feet. Side slopes will be 2:1 or flatter.
- All berms shall be machine compacted.

- Rock Check Dams** – Temporary rock check dams are small dikes (approximately three feet high) constructed at frequent intervals in drainage ways where silt fences and hay bale check dams are impractical due to high flow velocities. The primary function of these devices is to promote deposition of sediment and provide some filtering of runoff water. Check dams will be constructed with a 1.5 to 2.0 inch crushed stone core and a layer of peastone on the upstream face.

Installation:

- Check dams will be placed in drainage ways:
- downstream of stream crossing where high flow velocities make other sediment filtering devices impractical.
- Sediment shall be removed from rock check dams when sediment has accumulated to 50 percent of original height.
- Peat or other wetlands material will be excavated and stockpiled prior to rock check dam installation and replaced once construction is complete.

- Sediment Basins** – This is a temporary embankment/impoundment area, excavated pit or used as part of a permanent detention device with a controlled outlet(s), that is a combination of wet and dry storage areas are created. The purpose is to intercept and retain sediment during construction, reduce or abate undesirable deposition of sediment to the waters of the state and downstream properties.

Installation and Maintenance:

- Contributory drainage area less than 100 acres.
- Effective height of the basin is 15 feet or less.
- The product of the storage times the effective height should be less than 3,000.
- A minimum residence storage time of 10 hours for a 10 year frequency, 24 hour, Type III storm.
- Flood Routing by TR-55.
- Sediment storage volume shall be calculated by the Universal Soil Loss equation with an 80% trap efficiency for a predicted one year load.
- Minimum capacity volumes shall be 134 cubic yards of water storage per acre drained of disturbed area contributing to the basin.
- Sediment basins shall be cleaned when sediment accumulates to 50% of the net storage capacity. Dewater basin through pumping means prior to removing sediment. Material shall be removed and left to dry to an approved location.

- Energy Dissipators – Outlet Protection Level Spreaders** – This is a permanent device used to reduce depth and velocity of concentrated runoff and release it uniformly into a stable area. Except as otherwise noted, they shall be constructed of rip-rap stone.

Installation and Maintenance:

- Design flows for 10 year storms or less than 20 cfs.
- Length, width, and detail is as shown on the site plans and detail sheets.
- To be constructed on undisturbed earth.
- Inspect annually and repair immediately where erosion occurs.

- Hydrograss And Floc Log Specifications:**

- Pre-Construction:**
 - Send a soil sample directly to Applied Polymer Systems, Inc., 519 Industrial Drive, Woodstock, GA 30189, Attn: Steve Iwinski (678-494-5998) to determine the log, liquid, and crystal types most appropriate for the site soil type.
- Construction Phase Applications:**
 - Swales and Sedimentation Basins**
 - Two Floc Logs shall be placed at each check dam throughout the swale system.
 - Logs should be applied via 3 FT wood stakes and placed in running water areas of the swale.
 - 25 LBS/150 LF of Clarifying Crystal shall be applied to swales in a one time only application to jump start the logs.
 - Disturbed Soil Areas**
 - Apply wood fiber slurry to all disturbed areas. Slurry shall consist of 1,500 LBS of real wood fiber per acre, 2.5 gallons of Silt Stop Liquid Emulsion per acre, and 100 LBS of Guar Gum per acre.
 - An alternative to wood fiber slurry is to apply hay or straw mulch and cover with 25 LBS/AC of Silt Stop Clarifying Crystals with a mulch spreader.
- Check Dam Construction:**
 - Dams should consist of 1-3 inch stone formed in a U or V shape towards the sedimentation basin.
 - Three layers of Coconut Jute Matting should be applied to the inside of the check dam and secured with staples.
- Maintenance:**
 - Floc Logs shall be inspected after each major storm event.
 - Sediment buildup around Floc Logs shall be removed and the log reset when 50% of the log is no longer exposed.
 - Logs shall be replaced when the log is no longer performing as intended as specified by the manufacturer's technical representative.

D. CONTROL PLAN IMPLEMENTATION

In addition to the devices and schedules outlined in this soil erosion and sediment control plan, the following procedures will be followed by the earthwork contractor:

- The contractor shall inspect the effectiveness and condition of erosion control devices during storm events, after each rainfall of one-half inch magnitude or greater, prior to weekends, and prior to forecasted storm events.
- The contractor shall repair or replace damaged erosion control devices immediately, and in no case, more than four hours after observing such deficiencies.
- The contractor shall be prepared to implement interim drainage controls and erosion control measures as may be necessary during the course of construction.
- The contractor shall make available on-site all equipment, materials and labor necessary to effect emergency erosion control and drainage improvement within four hours of any impending emergency situation.
- The contractor shall make a final inspection, clean all cross culverts and sweep off roadways before the road is dedicated to the Town.
- The contractor shall have on call at all times a responsible representative who, when authorized, will mobilize the necessary personnel, materials and equipment and otherwise provide the required action when notified of any impending emergency situation.
- The contractor shall supply a telephone number to the Town Engineer and IW enforcement officer so that the contractor may be contacted during the evenings and on weekends, if necessary.?

E. PERMANENT CONTROL DEVICES

Following construction, erosion will be prevented by established vegetation cover and by permanent devices which include catch basins with sediment traps, grassed swales, natural filter traps, and outlet protection.

Through the strict implementation of this proposed soil erosion and sediment control plan, erosion of soils on the site will be minimized and contained to prevent sedimentation of site wetlands and adjacent and downstream properties and watercourses.

NO.	DATE	REVISION DESCRIPTION	DRAWN BY	CHECKED BY

DYMAR

800 Main Street South · Southbury, CT 06488 · (800) 387-1066 · Fax (800) 387-1871
ENGINEERING · PLANNING · SURVEYING · DEVELOPMENT SERVICES

NOT FOR CONSTRUCTION

CLIENT: Easton Racquet Club, Inc.
36 Wimbeldon Lane, P.O. Box 152
Easton, CT 06612

PROJECT: Easton Racquet Club, Inc.
36 Wimbeldon Lane, P.O. Box 152
Easton, CT 06612

TITLE: Sediment & Erosion Control Construction Standards

DATE: 02/15/21

SCALE: N.T.S.

DESIGNED BY: M.E.L.

DRAWN BY: C.C.B.


CHECKED BY: M.E.L.

JOB NO: 00395

DRAWING NO: C-5D


NOTE:
1. THE CONTRACTOR SHALL NOTIFY "CALL BEFORE YOU DIG" AT LEAST 72 HOURS PRIOR TO THE START OF EXCAVATION, BY CALLING 1-800-922-4455.

NOTES:
 1. LENGTH EQUAL TO 50' MINIMUM WHERE SOILS ARE SAND AND GRAVEL; PROVIDE 100' WHERE SOILS ARE PREDOMINANTLY CLAYS OR SILTS.
 2. SPECIFICATIONS: CRUSHED STONE - CONN DOT NO. 3 OR ASTM C-33, GRADE NO. 3; GEOTEXTILE FILTER FABRIC - MIRAF 500X OR APPROVED EQUAL.




ANTI-TRACKING PAD DETAIL
 N.T.S.

NOTES:
 1. AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE.
 2. MAXIMUM SLOPE OF STOCKPILE SHALL BE 2:1.
 3. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE SURROUNDED WITH EITHER SILT FENCING OR STRAWBALES, THEN STABILIZED WITH VEGETATION OR COVERED WITH POLYETHYLENE SHEETING.
 4. TO BE USED WHERE TOPSOIL IS NECESSARY FOR REGRADING AND VEGETATING DISTURBED AREAS, TOPSOIL IS APPLIED TO SUBSOILS THAT ARE DRAUGHTY (HAVING LOW AVAILABLE MOISTURE FOR PLANTS), STONEY, SALTY, HAVE LOW PERMEABILITY, OR ARE EXTREMELY ACID. IT IS ALSO USED TO BACKFILL AROUND SHRUB AND TREE TRANSPLANTS. PRESERVATION OF EXISTING TOPSOIL IS BENEFICIAL FOR ALL TYPES OF LAWN OR ORNAMENTAL PLANTINGS.
 5. TEMPORARY STOCKPILE STABILIZATION MEASURES INCLUDE VEGETATIVE COVER, MULCH, NONVEGETATIVE COVER, AND PERIPHERAL SEDIMENT TRAPPING BARRIERS. THE STABILIZATION MEASURE(S) SELECTED SHOULD BE APPROPRIATE FOR THE TIME OF YEAR, SITE CONDITIONS, AND REQUIRED PERIOD OF USE.
 6. SEE EROSION AND SEDIMENT CONTROL PLAN FOR LOCATIONS.




SOIL STOCKPILE DETAIL
 N.T.S.

NOTES:
 1. MAX. AREA DRAINAGE TO A BARRIER IS ONE ACRE OR LESS WITH SLOPE GRADIENT BEHIND A BARRIER LIMITED TO 2H:1V.
 2. MAX. DISTANCE ON SLOPES BETWEEN BARRIERS IS 100' WITH ALLOWABLE FLOWS RECEIVED AT CHECK DAMS UP TO ONE C.F.S.
 3. STRAW BALES SHALL BE INSPECTED PERIODICALLY AND SHALL BE REMOVED AND REPLACED AFTER 3 MONTHS EXCEPT AS OTHERWISE DIRECTED BY THE ENGINEER OR ENFORCEMENT OFFICIAL. BALES SHALL NOT BE REMOVED UNTIL UPSLOPE AREAS HAVE BEEN PERMANENTLY STABILIZED.




TYPICAL STRAW BALE INSTALLATION DETAIL
 N.T.S.

NOTES:
 1. TAPER TRANSITION FOR CHANNEL INSTALLATIONS AS REQUIRED TO MATCH CHANNEL WIDTH, OR AS INDICATED ON THE PLANS.
 2. ALL TOTAL WIDTHS AND LENGTHS FOR SPREADER PAD INSTALLATIONS ARE AS INDICATED ON PLANS.




RIPRAP SPLASHPAD DETAIL
 N.T.S.




TYPICAL CURTAIN DRAIN DETAIL
 N.T.S.

NOTES:
 1. SILT FENCE STAKE SPACING MAY VARY AS PER MANUFACTURERS RECOMMENDATIONS. MAXIMUM SPACING IS 8'-0".
 2. JOIN SILT FENCE SECTIONS BY OVERLAPPING END STAKES TO PREVENT SILT FROM BYPASSING ADJOINING UNITS. INSPECT PERIODICALLY AND REMOVE SILT WHEN MORE THAN 1/2 THE HEIGHT IS FILLED ON THE UPPER FENCE.
 3. REPLENISH OR REPLACE HAY OR WOOD CHIPS AS INSTRUCTED BY E&S INSPECTOR.




DOUBLE FILTER FABRIC FENCE WITH BATTON DETAIL
 N.T.S.

NOTES:
 1. SPACING MAY VARY AS PER MANUFACTURERS RECOMMENDATIONS. MAXIMUM SPACING IS 8'-0".
 2. JOIN SILT FENCE SECTIONS BY OVERLAPPING END STAKES TO PREVENT SILT FROM BYPASSING ADJOINING UNITS.
 3. INSPECT PERIODICALLY AND REMOVE SILT WHEN MORE THAN 1/2 THE HEIGHT IS FILLED.
 4. APPLY CRYSTALLINE POLYMER DOWN GRADIENT OF FENCE PER MANUFACTURER'S RECOMMENDATIONS WHEN CONSTRUCTION ZONE IS WITHIN 100 FEET OF A WETLAND OR WATERCOURSE.



FILTER FABRIC FENCE DETAIL
 N.T.S.


TYPICAL SIDEWALK BITUMINOUS CONCRETE PAVEMENT DETAIL
 N.T.S.



FENCE SCHEDULE		
POST OR RAIL TYPE	H @ 4FT AND 5FT HIGH FENCE	H @ 6FT TO 10FT HIGH FENCE
TERMINAL OR CORNER POST	2 1/2"	3"
LINE POST	2"	2 1/2"
TOP RAIL	1 5/8"	1 5/8"
MID RAIL	NONE	1 5/8"
BOTTOM RAIL	1 5/8"	1 5/8"
GATE POST	3"	3"
GATE FRAME	3"	2"


NOTE: INSTALL FENCE TOPPER, OR APPROVED EQUAL, ON ALL FENCES AND GATES FOR H @ 5 FEET OR LESS.

NOTES:
 1. ALL FENCING COMPONENTS TO BE VINYL COATED, COLOR BY CLIENT, INCLUDE WITH SUBMITTALS FOR APPROVAL.
 2. ALL CONCRETE SHALL BE CLASS 'A' WITH A MINIMUM COMPRESSION STRENGTH OF 3,000 PSI.
 3. STANDARD FABRIC SHALL BE 2" MESH, 9 GAUGE; FABRIC MESH FOR TENNIS COURTS SHALL BE 1-3/4", AND MESH FOR HEIGHTS AT 4' OR LESS SHALL BE 1".
 4. VINYL INFILL SLATS SHALL BE PROVIDED ONLY IF INDICATED ON THE SITE LAYOUT OR LANDSCAPE PLANS.
 5. 9 GAUGE WIRE TIES SHALL BE SPACED @24" MAX ALONG HORIZONTAL RAILS AND @ 12" MAX FOR VERTICAL POSTS.




TYPICAL CHAIN LINK FENCE DETAIL
 N.T.S.

NOTES:
 1. REFERENCE IS MADE TO "TYPICAL CHAIN LINK FENCE DETAIL" FOR POST AND RAIL SCHEDULE AND SPECIFICATIONS.
 2. GATE SHALL BE COMPLETED WITH BALL AND SOCKET HINGES THAT ARE SELF CLOSING, OR APPROVED EQUAL. SUBMIT SHOP DRAWINGS FOR APPROVAL.
 3. ALL GATES TO OPEN OUTWARD EXCEPT OTHERWISE SHOWN.




PEDESTRIAN GATE DETAIL
 N.T.S.


NOTES:
 1. 4,000 PSI CONCRETE SHALL BE USED FOR ALL PRECAST BASES, SUMPS, TRANSITION, RISER AND CORBEL SECTIONS. REINFORCING AND SPECIFICATIONS SHALL CONFORM TO ASTM C-478, LATEST REVISED EDITION.



PRECAST CONCRETE YARD DRAIN DETAIL
 N.T.S.



TREE PROTECTION DETAIL
 N.T.S.



EVERGREEN TREE PLANTING DETAIL
 N.T.S.

NOTE:
 1. THE CONTRACTOR SHALL NOTIFY "CALL BEFORE YOU DIG" AT LEAST 72 HOURS PRIOR TO THE START OF EXCAVATION, BY CALLING 1-800-922-4455.


NO.	DATE	DESCRIPTION	DRAWN BY	CHECKED BY
1	3-26-21	Added Riprap Outlet Detail.	S.A.L.	M.E.L.

DYMAR
 800 Main Street South · Southbury, Ct. 06488 · (203) 267-1066 · Fax (203) 267-1547
 ENGINEERING · PLANNING · SURVEYING · DEVELOPMENT SERVICES
 DRAWINGS TO BE USED FOR LAND USE SUBMISSIONS ONLY
NOT FOR CONSTRUCTION

CLIENT: Easton Racquet Club, Inc.
 36 Wimbeldon Lane, P.O. Box 152
 Easton, CT 06612
 PROJECT: Easton Racquet Club, Inc.
 36 Wimbeldon Lane, P.O. Box 152
 Easton, CT 06612
 TITLE: Sediment & Erosion Control Details
 & Misc. Site Details


DATE	SCALE	AS NOTED	M.E.L.
02/15/21			
DESIGNED BY	DRAWN BY	C.C.B.	M.E.L.
CHECKED BY	M.E.L.	003315	
JOB NO:			
DRAWING NO:			

C-5E




PICKLEBALL NET CENTER STRAP ANCHOR
N.T.S.


- NOTES:
- ALL DIMENSIONS ARE TO THE OUTSIDE EDGE OF LINES.
 - ALL PLAYING LINES ARE 2" IN WIDTH.
 - NET SPECIFICATIONS:
 - THE NET MADE OF ANY MATERIAL THAT WILL NOT ALLOW A BALL TO PASS THROUGH IT.
 - THE NET SHOULD BE 21'-9" LONG, EXTENDING FROM ONE POST TO ANOTHER. THE NET HEIGHT FROM THE BOTTOM EDGE SHOULD BE AT LEAST 30".
 - THE NET SHALL BE SUSPENDED OVER THE CENTER OF THE COURT. THE TOP SHALL BE 36" ABOVE GRADE AT THE SIDELINES AND A MINIMUM 34" AT THE MIDPOINT.
 - A CENTER STRAP IS RECOMMENDED FOR A PERMANENT NET AND MUST BE PLACED AT THE CENTER OF THE NET TO ALLOW FOR THE ADJUSTMENT OF THE NET TO MAINTAIN THE MINIMUM 34" HEIGHT.
 - THE TOP OF THE NET SHOULD BE EDGED WITH A 2-INCH WHITE TAPE BINDING OVER A CORD OR CABLE RUNNING THROUGH THE BINDING. THIS BINDING MUST REST UPON THE CORD OR CABLE.
 - NET POSTS SHOULD BE 22'-0" FROM INSIDE POST TO INSIDE POST, THE MAXIMUM DIAMETER SHOULD BE 3".




TYPICAL PICKLEBALL COURT PLAYING LINE LAYOUT
SCALE: 1/4"=1'




ASPHALT PICKLEBALL COURT SECTION
N.T.S.




PICKLEBALL NET POST FOOTING
N.T.S.




GRAVEL UNDERDRAIN AT COURT EDGES DETAIL
N.T.S.



PICKLEBALL COURT EXPANSION JOINT DETAIL
N.T.S.



FOUR BAY PICKLEBALL COURT LAYOUT
SCALE: 1/8"=1'



PLAYERS BENCH
N.T.S.

NO.	DATE	REVISION DESCRIPTION	DRAWN BY	CHECKED BY

DYMAR
800 Main Street South - Southbury, Ct. 06488 - (203) 267-1066 - Fax (203) 267-1547
ENGINEERING · PLANNING · SURVEYING · DEVELOPMENT SERVICES

DRAWINGS TO BE USED FOR LAND USE SUBMISSIONS ONLY
NOT FOR CONSTRUCTION

CLIENT: **Easton Racquet Club, Inc.**
36 Wimbledon Lane, P.O. Box 152
Easton, CT 06612


PROJECT: **Easton Racquet Club, Inc.**
36 Wimbledon Lane, P.O. Box 152
Easton, CT 06612

TITLE: **Pickleball Court Details**

DATE:	02/15/21
SCALE:	AS NOTED
DESIGNED BY:	M.E.L.
DRAWN BY:	C.C.B.
CHECKED BY:	M.E.L.
JOB NO.:	00335
DRAWING NO.:	C-6A


NOTE:
1. THE CONTRACTOR SHALL NOTIFY "CALL BEFORE YOU DIG" AT LEAST 72 HOURS PRIOR TO THE START OF EXCAVATION, BY CALLING 1-800-922-4455.

NOTE:
1. DESIGN LIVE LOAD - 40 LBS/SQ. FT.




FRAMING PLAN

SCALE: 1/8" = 1'-0"




COURT MARKINGS

SCALE: 1/8" = 1'-0"




END ELEVATION



FOUNDATION PLAN


SCALE: 1/8" = 1'-0"



SIDE ELEVATION


TYPICAL PADDLE TENNIS COURT ELEVATIONS

SCALE: 1/8" = 1'-0"



TYPICAL STRUCTURAL MEMBERS

SCALE: 3" = 1'-0"



800 Main Street South - Southbury, Ct. 06488 - (203) 267-1066 - Fax (203) 267-1547
ENGINEERING · PLANNING · SURVEYING · DEVELOPMENT SERVICES

DRAWINGS TO BE USED FOR LAND USE SUBMISSIONS ONLY
NOT FOR CONSTRUCTION

CLIENT: Easton Racquet Club, Inc.
36 Wimbledon Lane, P.O. Box 152
Easton, CT 06612

PROJECT: Easton Racquet Club, Inc.
36 Wimbledon Lane, P.O. Box 152
Easton, CT 06612

TITLE: Paddle Ball Court Details

DATE	02/15/21
SCALE	AS NOTED
DESIGNED BY	M.E.L.
DRAWN BY	C.C.B.
CHECKED BY	M.E.L.
JOB NO.	00335
DRAWING NO.	C-6B

NOTE:
1. THE CONTRACTOR SHALL NOTIFY "CALL BEFORE YOU DIG" AT LEAST 72 HOURS PRIOR TO THE START OF EXCAVATION, BY CALLING 1-800-922-4455.

C-6B

1 2


1 2

1 2


NO.	DATE	REVISION	DESCRIPTION	DRAWN BY	CHECKED BY

COPYRIGHT © 2021, THESE PLANS ARE THE PROPERTY OF DYMAR, PREPARED AS AN INSTRUMENT OF SERVICE FOR THE PROJECT AND ARE NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM. THE CONTRACTOR SHALL VERIFY ALL FIELD CONDITIONS AND DIMENSIONS AND IS RESPONSIBLE FOR NOTIFYING DYMAR IF A DISCREPANCY EXISTS, THEREAFTER DYMAR SHALL HAVE FINAL SAY.

NOTES:
 1. LIGHTING SUPPLIED BY LEE TENNIS (877-4HARTRO) OR APPROVED EQUAL.
 2. CATALOG NO: ELSO-1001.



LG1 130C
 TENNIS COURT LIGHTING POLE & LUMINAIRE DETAIL
 N.T.S.



Luminaire Schedule						
Symbol	Qty	Label	Arrangement	LLF	Description	Lum. Watts
⚡	24	S2	2 @ 90 DEGREES	1.000	VUE-3-TT-144L-1-50K-D90° @ 29' MTG. HT.	458
⚡	3	S4	4 @ 90 DEGREES	1.000	VUE-3-TT-144L-1-50K-4@90° @ 29' MTG. HT.	458

Calculation Summary						
Label	Units	Avg	Max	Min	Avg/Min	Max/Min
calcs	Fc	10.76	63.4	0.0	N.A.	N.A.
COURT 1	Fc	48.98	56.8	41.0	1.19	1.39

NLS LIGHTING
 EASTON RACQUET CLUB
 LIGHTING AFFILIATES
 DATE:01/17/21

DYMAR
 800 Main Street South - Southbury, Ct. 06488 - (203) 267-1066 - Fax (203) 267-1547
 ENGINEERING · PLANNING · SURVEYING · DEVELOPMENT SERVICES

CLIENT: Easton Racquet Club, Inc.
 36 Wimbledon Lane, P.O. Box 152
 Easton, CT 06612
 PROJECT: Easton Racquet Club, Inc.
 36 Wimbledon Lane, P.O. Box 152
 Easton, CT 06612
 TITLE: Tennis Courts & Pickle Ball Courts
 Photometric and Lighting Details

DATE: 02/15/21
 SCALE: 1"=30'
 DESIGNED BY: M.E.L.
 DRAWN BY: C.C.B.
 CHECKED BY: M.E.L.
 JOB NO: 003335
 DRAWING NO: C-7A

NOTE:
 1. THE CONTRACTOR SHALL NOTIFY "CALL BEFORE YOU DIG" AT LEAST 72 HOURS PRIOR TO THE START OF EXCAVATION, BY CALLING 1-800-922-4455.


NO.	DATE	REVISION DESCRIPTION

DRAWN BY: _____
 CHECKED BY: _____

COPYRIGHT © 2021, THESE PLANS ARE THE PROPERTY OF DYMAR, PREPARED AS AN INSTRUMENT OF SERVICE. PROJECT DYMAR DOES NOT GUARANTEE THESE PLANS TO REFLECT THE TRUE CONDITIONS. THE CONTRACTOR SHALL VERIFY ALL FIELD CONDITIONS AND DIMENSIONS AND IS RESPONSIBLE FOR NOTIFYING DYMAR IF A DISCREPANCY EXISTS. THESE PLANS SHALL HAVE FINAL SAY.


DRAWINGS TO BE USED FOR LAND USE SUBMISSIONS ONLY
 NOT FOR CONSTRUCTION

NOTES:
 1. LIGHTING SUPPLIED BY LEE TENNIS (877-4HARTRU) OR APPROVED EQUAL.
 2. CATALOG No: ELS00-T001.



TENNIS COURT
 LIGHTING POLE & LUMINAIRE DETAIL
 N.T.S.


LGT
 130c




SITE LIGHTING POLE FOUNDATION
 N.T.S.

LGT
 184B

- NOTES:
- LUMINAIRES MOUNTED AT 15' ABOVE FINISHED DECK.
 - MAINTAINED ILLUMINANCE @ 90% LUMEN MAINTENANCE GROUND REFLECTANCE = 7%.
 - HORIZONTAL ILLUMINANCE MEASURED AT GRADE, VERTICAL ILLUMINANCE MEASURED AT 5' ABOVE GRADE.
 - ALL ILLUMINANCE MEASURED IN FOOT-CANDLES.



EXISTING PADDLE COURT LIGHTING




ALL PADDLE COURT LIGHTING

LUMINAIRE SCHEDULE

TAG	QTY	DESCRIPTION	LUM. WATTS	DELIVERED LUMENS	LLF
A	12	AREAFLD1A145UNVD840T5BZ WITH VISOR	145.5	N/A	0.90
B	12	LSMT-2CXBT4TF	280.0	N/A	0.90

CALCULATION SUMMARY

LABEL	CALC. TYPE	UNITS	AVG.	MAX.	MIN.	AVG/MIN	MAX./MIN.
GROUND	ILLUMINANCE	FC	2.99	90.7	0.0	N/A	N/A
WETLANDS	ILLUMINANCE	FC	0.37	2.6	0.0	N/A	N/A



800 Main Street South · Southbury, CT 06488 · (800) 287-1046 · Fax (800) 287-1547
 ENGINEERING · PLANNING · SURVEYING · DEVELOPMENT SERVICES

DRAWINGS TO BE USED FOR LAND USE SUBMISSIONS ONLY

NOT FOR CONSTRUCTION

CLIENT: Easton Racquet Club, Inc.
 36 Wimbeldon Lane, P.O. Box 152
 Easton, CT 06612

PROJECT: Easton Racquet Club, Inc.
 36 Wimbeldon Lane, P.O. Box 152
 Easton, CT 06612

TITLE: Paddle Board Courts
 Photometric and Lighting Details

DATE: 02/15/21

SCALE: 1"=30'

DESIGNED BY: M.E.L.

DRAWN BY: C.C.B.


CHECKED BY: M.E.L.

JOB NO: 00395

DRAWING NO: C-7C

1 2

NOTE:
 1. THE CONTRACTOR SHALL NOTIFY "CALL BEFORE YOU DIG" AT LEAST 72 HOURS PRIOR TO THE START OF EXCAVATION, BY CALLING 1-800-922-4455.



TECHLIGHT

FEATURES & SPECIFICATIONS

APPLICATION – The High Lumen output luminaire is designed to be a replacement for HID fixtures up to 1000W. It is optional for lighting applications where long life, low maintenance, and consistent color rendering is required. Areas with limited accessibility due to future location or where heavy pedestrian or vehicle traffic makes maintenance difficult are ideal applications. The high wattage luminaire allows the fixture to be used for parking, residential, quick service, shopping centers or sports lighting applications.

CONSTRUCTION – The heavy duty housing is constructed of cast aluminum with heat dissipating fins. The optical assemblies are sealed in place using a silicone gasket for weather light protection. Modular LED system for ease of maintenance. ETL listed for wet locations (IP64). Additional IP66 rating available upon request. Each fixture comes standard with prep-wired to accommodate advanced wireless control, management and reporting systems for outdoor lighting.

FINISH – A corrosion-resistant black E-Coat layer that forms a uniform and all-encompassing protective barrier is applied to the fixture prior to electrostatically applying a super durable powder coat finish. Standard colors available: Black, Bronze, US Green, White. Custom colors available upon request.

OPTICAL SYSTEM – Made with a state of the art UV stabilized acrylic high performance refractive optical assemblies that use high transmittivity materials to achieve precise photometric distributions. Available in Type II, III, IV, Automotive, Automotive Frontline Wide, V, Tennis, V Narrow, V Medium and V Wide beam configurations. Optics may be ordered rotated 90 degrees for perimeter lighting or walkway applications (optics are not field rotatable). The full cutoff fixture is Street Light Friendly (meets or exceeds Dark Sky requirements) in the horizontal position.


ELECTRICAL SYSTEM – Available in up to a 8 brick LED system in 5000K-70 CRI Cool White (or 5000K or 4000K CRI Neutral White color temperatures programmed with CREER™ XLamp XHP70 LEDs). Consult factory for high CRI (90+) model availability. Available with 100-300V 50/60Hz AC Class I lower supply LED's rated for over 50,000 hours at 25°C ambient temperature. 347V-480V input option available. 0-10V dimming. Built-in surge protection up to 10 kV. Built-in Active PFC Function 90%+ Total LED Power Supply conforms to UL8750 standards and is IP66 rated for wet locations.

MOUNTING – The fixture was designed to utilize an innovative die cast decorative arm that allows the fixture to easily mount to almost any existing pole pattern or new pole. Additional mounting options include a quick mount with 8" straight arm (for use on fixtures with no more than 4 LED bricks) and a 2" adjustable slip filter for tension mounting (for use as a downlight only). Additional mounting options may be available for custom applications.

LISTINGS – LED Power Supply listed for wet locations (IP65). LED bricks ETL listed for wet locations (IP64). Meets US and Canadian safety standards. -40°C to 50°C ambient operation. RoHS Compliant.

Project	Type

High Lumen Output Scimitar LED Area Light LSMT Series



Series	Housing Height	Length x Width	EPA (ft)
LSMT	5.23"	37.23" x 16.02"	1.4

ORDERING INFORMATION

Example: **LSMT8X6T5WH1-BZ**

Series	# of Bricks	Color Temp	# LEDs per Brick	Optics	Drive Current	Voltage	Options	Finish
LSMT	8	6000K	2000	T2	1400 mA	120-277V	None	Black


NOTES:
 1. Multi-Volt is an auto-ranging power supply from 100V to 300V input.
 2. Custom color, color rendering is available. Contact your sales representative.
 3. QMS/CR (Dark Mount with 8" Straight Arm or Black Mount) is available for fixtures with up to 4 bricks.
 4. Additional IP66 rating may not be charged once production has begun on the fixture.

Accessories (Order as separate line items)

SDARM	Die Cast Decorative Arm Mount (Square Pole, 1.4 EPA)	PCRT	7.5" Tall Lock Protocol Receipt Arm C13141
QMS/CR	Quick Mount with 8" Straight Arm (Black Mount)	PCF	480V Tall Lock Protocol
SD21*	Angle Back Light Shield	PCB	Multi-Tap (105-285V) Tall Lock Protocol

LSMT Scimitar High Lumen Output Area Light

PHOTOMETRICS



EPA RATINGS (ft²)

Area Mount	1 or 2 Bricks	4 Bricks	6 Bricks
10' x 10'	1.0	1.3	1.6
10' x 12'	2.0	2.6	3.2
10' x 14'	1.9	2.4	3.0
10' x 16'	2.5	3.3	4.0
10' x 18'	3.5	4.5	5.5

MOUNTING ACCESSORIES



ADDITIONAL FIXTURE ACCESSORIES

SD21*	Angle Back Light Shield	PCRT	7.5" Tall Lock Protocol Receipt Arm C13141
QMS/CR	Quick Mount with 8" Straight Arm or Black Mount	PCF	480V Tall Lock Protocol
PCB	Multi-Tap (105-285V) Tall Lock Protocol		


LSMT Scimitar High Lumen Output Area Light

LUMINAIRE CHARACTERISTICS

1400 mA Drive Current

# of LED Bricks	Drive Current	Color Temp	Type II	Type III	Type IV	Type 4A	Type 4B	FAW	Type SE	Type SM	Type SW	System Voltage	L70 @25°C	Amperage Draw
18BRK	1400 mA	Cool White (5000K)	14093	14658	16407	16062	15418	15477	17172	17313	15542	147	>50K	1.23 A
9BRK	700 mA	Cool White (5000K)	29933	29136	32814	32124	3030	3055	34274	34266	31084	249	>50K	2.46 A
4BRK	350 mA	Cool White (5000K)	59971	58331	65628	64247	61672	61909	68548	69252	62167	588	>50K	4.90 A
6BRK	420 mA	Cool White (5000K)	89957	87947	98442	96371	92508	92864	102823	103877	92521	882	>50K	7.35 A
18BRK	1400 mA	Neutral White (4000K)	14520	14994	15376	15444	14825	14882	16478	16647	14944	147	>50K	1.23 A
9BRK	700 mA	Neutral White (4000K)	28640	28188	31552	30888	29650	29764	32956	33294	29888	294	>50K	2.45 A
4BRK	350 mA	Neutral White (4000K)	57280	56376	63104	61776	59300	59528	65913	66588	59776	588	>50K	4.90 A
6BRK	420 mA	Neutral White (4000K)	85920	84564	94656	92664	89150	89255	98688	99882	89664	882	>50K	7.35 A

ADDITIONAL FIXTURE DIMENSIONS



WARNING: Maintenance performed including the replacement of LED bricks while power is still supplied to the luminaire may result in system failures and will void the warranty.

TECHLIGHT
 2707 Saturnus Drive
 Dallas, TX, 75229
 Phone: 214-350-9191, 800-225-0777, Fax: 214-350-9137
 www.techlight.com

www.sylvania.com/luminaires

SYLVANIA Luminaires Area Light

Application

The Area Light luminaires are the perfect alternative to traditional lighting technologies offering a variety of solutions to illuminate parking lots, parking garage roofs and general area lighting.

Features

- Integrated photocontrol receptacle compatible with up to 7 pin photosensors
- Slim design with multiple mounting and distribution options
- Robust fixture with IP66 and 3G Vibration rating
- Energy savings up to 68%
- Offered in 70, 110, 145 and 220 watts
- CR1 80+
- 4000K and 5000K color temperature
- Up to 130 LPW
- Type III, IV, V distribution
- UV stabilized polycarbonate lens
- Power factor >90%
- 0-10V dimmable
- Constant current LED driver with 4kV surge suppression

Wattage Comparison

Traditional Source	Traditional System Wattage	LED System Wattage	Energy Savings
100W HPS	120	70	42%
150W MH	180	70	61%
175W MH	210	70	67%
250W HPS	295	110	63%
300W MH	360	110	69%
400W MH	460	145	69%
750W HPS	840	220	74%
1000W MH	1080	220	80%
1000W HPS	1100	220	80%

Rated Life

≥140,000 hours (L70)

Warranty

Standard 5-year luminaire warranty (LEDLUM001)

Ambient Operating Range

-40°F to +104°F (-40°C to +40°C)

Fixture Certifications and Listings

cULus listed to UL1598 standards for wet locations and IP66 rated

Driver meets UL1310 and UL48 Class I



LEDLUM019R6 9-18

Ordering Guide

AREALD	1A	/ XXX	UNV	D	8	XX	/ XX	/ BZ	/ X
--------	----	-------	-----	---	---	----	------	------	-----

Product Name: 1A
 Voltage: 120-277V
 Dimming: CR1
 Color Temp (CCT): 50-5000K
 Distribution: T2-T5
 Color/Finish: BZ=Black, D=Motor Daylight, TS=Type V

Ordering Information

Item Number	Ordering Abbreviation	Wattage (W)	Input Voltage (V)	Dimming (CR1)	Color Temp (CCT)	Distribution	Color/Finish	Total Lumens	DLG	LPW**	Options	BUG Rating
70556	AREALD1A10UNV6000T5BZ	70	120-277	0-10V	>80	4000K	Type III	8,100	Prm	116	None	82-UG-02
71078	AREALD1A10UNV6000T5D2	70	120-277	0-10V	>80	4000K	Type IV	8,200	Prm	117	None	82-UG-02
71079	AREALD1A10UNV6000T5D2	70	120-277	0-10V	>80	4000K	Type V	8,500	Prm	121	None	82-UG-01
71113	AREALD1A10UNV5000T5BZ	70	120-277	0-10V	>80	5000K	Type III	8,600	Prm	123	None	82-UG-02
71137	AREALD1A10UNV5000T5BZ	70	120-277	0-10V	>80	5000K	Type IV	8,700	Prm	125	None	82-UG-02
71171	AREALD1A10UNV5000T5BZ	70	120-277	0-10V	>80	5000K	Type V	9,000	Prm	130	None	82-UG-01
60386	AREALD1A10UNV6000T5BZ	70	347-480	0-10V	>80	4000K	Type III	8,100	Prm	116	None	82-UG-02
60387	AREALD1A10UNV6000T5BZ	70	347-480	0-10V	>80	4000K	Type IV	8,200	Prm	117	None	82-UG-02
60388	AREALD1A10UNV6000T5BZ	70	347-480	0-10V	>80	4000K	Type V	8,500	Prm	121	None	82-UG-01
60389	AREALD1A10UNV6000T5BZ	70	347-480	0-10V	>80	4000K	Type III	8,600	Prm	123	None	82-UG-02
60390	AREALD1A10UNV6000T5BZ	70	347-480	0-10V	>80	4000K	Type IV	8,700	Prm	125	None	82-UG-02
60391	AREALD1A10UNV6000T5BZ	70	347-480	0-10V	>80	4000K	Type V	9,000	Prm	130	None	82-UG-01
60337	AREALD1A10UNV6000T5BZ	110	120-277	0-10V	>80	4000K	Type III	12,600	Prm	117	None	82-UG-02
60338	AREALD1A10UNV6000T5BZ	110	120-277	0-10V	>80	4000K	Type IV	12,700	Prm	117	None	82-UG-02
60339	AREALD1A10UNV6000T5BZ	110	120-277	0-10V	>80	4000K	Type V	13,300	Prm	123	None	82-UG-01
60340	AREALD1A10UNV6000T5BZ	110	120-277	0-10V	>80	5000K	Type III	13,300	Prm	124	None	82-UG-03
60341	AREALD1A10UNV6000T5BZ	110	120-277	0-10V	>80	5000K	Type IV	13,300	Prm	125	None	82-UG-02
60342	AREALD1A10UNV6000T5BZ	110	120-277	0-10V	>80	5000K	Type V	13,300	Prm	124	None	82-UG-02
60382	AREALD1A10UNV6000T5BZ	110	347-480	0-10V	>80	4000K	Type III	13,300	Prm	117	None	82-UG-01
60383	AREALD1A10UNV6000T5BZ	110	347-480	0-10V	>80	4000K	Type IV	12,700	Prm	117	None	82-UG-01
60384	AREALD1A10UNV6000T5BZ	110	347-480	0-10V	>80	4000K	Type V	13,300	Prm	124	None	82-UG-03
60385	AREALD1A10UNV6000T5BZ	110	347-480	0-10V	>80	5000K	Type III	13,300	Prm	125	None	82-UG-03
60386	AREALD1A10UNV6000T5BZ	110	347-480	0-10V	>80	5000K	Type IV	13,300	Prm	125	None	82-UG-02
60387	AREALD1A10UNV6000T5BZ	110	347-480	0-10V	>80	5000K	Type V	13,300	Prm	124	None	82-UG-02
60388	AREALD1A10UNV6000T5BZ	110	347-480	0-10V	>80	4000K	Type III	17,900	Prm	122	None	82-UG-02
60389	AREALD1A10UNV6000T5BZ	110	347-480	0-10V	>80	4000K	Type IV	17,900	Prm	117	None	82-UG-03
60390	AREALD1A10UNV6000T5BZ	110	347-480	0-10V	>80	5000K	Type III	17,900	Prm	117	None	82-UG-03
60391	AREALD1A10UNV6000T5BZ	110	347-480	0-10V	>80	5000K	Type IV	17,900	Prm	123	None	82-UG-02
60392	AREALD1A10UNV6000T5BZ	110	347-480	0-10V	>80	5000K	Type V	17,900	Prm	123	None	82-UG-03
60393	AREALD1A10UNV6000T5BZ	145	120-277	0-10V	>80	4000K	Type III	17,900	Prm	117	None	82-UG-03
60394	AREALD1A10UNV6000T5BZ	145	120-277	0-10V	>80	4000K	Type IV	17,900	Prm	117	None	82-UG-03
60395	AREALD1A10UNV6000T5BZ	145	120-277	0-10V	>80	5000K	Type III	17,900	Prm	118	None	82-UG-03
60396	AREALD1A10UNV6000T5BZ	145	120-277	0-10V	>80	5000K	Type IV	17,900	Prm	117	None	82-UG-02
60397	AREALD1A10UNV6000T5BZ	145	120-277	0-10V	>80	5000K	Type V	17,900	Prm	122	None	82-UG-02
60398	AREALD1A10UNV6000T5BZ	145	120-277	0-10V	>80	5000K	Type III	17,900	Prm	117	None	82-UG-03
60399	AREALD1A10UNV6000T5BZ	145	120-277	0-10V	>80	5000K	Type IV	17,900	Prm	117	None	82-UG-03
60400	AREALD1A10UNV6000T5BZ	145	120-277	0-10V								